## ENVIRONMENTAL SYSTEMS LLC.

2358 HWY# 23 MORA MN. 55051 Ph. 320-241-7036 07/10/2024

## TIMED DOSE TYPE III DESIGN

**LOCATION: 32586 HWY 123** 

SANDSTONE MN.

PID; R30.0461.001

S13-TWP042-R020

**OWNER: RUSSELL and KAREN THOMAS** 

**SYSTEM TYPE:** TYPE III MOUND

**DESIGN FLOW:** 5 BEDROOM DESIGNED @ 638 GPD

TREATMENT AREA: 850 SQ.FT. ROCK BED

**SLOPE:** 7%

**KEVIN HERWIG M.P.C.A #3945** 

# ENVIRONMENTAL SYSTEMS LLC. DESIGN-INSPECTION

07/10/2024

#### CONSTRUCTION NOTES & MATERIALS

PRODUCT BRAND & MODEL LISTED IN DESIGN MUST BE USED:

**BROWN-WILBERT 2500 SPLIT SEPTIC TANK** 

BROWN-WILBERT 2000 PUMP TANK
GOULDS WE511HH PUMP

EFFLUENT FILTER POLYLOK #PL-122 W/ALARM
INSTALL A TWO-WAY CLEANOUT IS TO BE INSTALLED 1
FOOT OUTSIDE HOME

FLOW CONTROL, TIMED DOSE, AND ALARM: SJE RHOMBUS MOD# IFS11W114H-8AC17G1J

IT IS THE DESIGNER'S DISCRETION TO APPROVE OR DISAPPROVE SUBSTITUTIONS. THE INSTALLER WILL BE RESPONSIBLE FOR DESIGN CHANGE FEE.

**KEVIN HERWIG LIC # 3945** 

## MOUND SYSTEM EXPANSION AND UPGRADE ON EXISTING SITE TYPE III MOUND

The existing mound including the topsoil, loam cover, rock bed and sand will be removed down to an elevation of 97.60 (any existing sand is to be jar tested. If the sand does not pass the jar test the old sand must be removed, surface roughed up and new send added to elevation)

The elevation of new rock and sand interface 100.60

The sand depth will be verified at the time of removal.

New washed sand will be added to achieve a minimum of 3' on upslope side of rock bed.

The elevation of top of sand will be 100.60

This mound expansion is to the east and to the north

New washed rock will be added (6" depth) approximate lateral elevation 101.10 3 new 2" laterals 83' long with 7/32" holes spaced at 3' will be placed on rock bed. 12" of loam and 6" of topsoil, seed and mulch to finish.

The existing septic tank is to be pumped and used as a holding tank during the drying period and construction of the mound.

The area <u>must be allowed</u> to dry to as long as necessary after removal and before new construction will begin.

#### Extreme care must be taken to protect this site!

All work will be completed to 7080 rule.

All rock, pipe, and debris removed from the mound is to be disposed of off-site.

Benchmark is the bottom of the house siding Elevation. 100.00

KEVIN HERWIG M.P.C.A. Lic # 3945

# TANK INSTALLATION AND CONSTRUCTION SPECIAL NOTES

# \*\*\*THE SEPTIC TANK AND PUMP TANK ON THIS SITE MAY NEED TO BE ANCHORED\*\*\*

SEE OPTIONAL ANCHORING DETAIL INCLUDED IN THIS DESIGN

#### **TANKS SPECS.**

SEPTIC TANK- BROWN WILBERT 2500 GAL.

**PUMP TANK- BROWN WILBERT 2000 GAL** 

#### **ANCHOR BLOCK SPECS.**

2'X2'X6' CONCRETE ANCHOR BLOCKS APROX WEIGHT 3700 LB ( USE AS MANY AS REQUIRED TO OFF SET BUOYANCY OF TANK A MINIMUM OF 2 PER TANK 1 ON EACH SIDE )


# TANK ANCHORING DETAIL

#### MATERIAL LIST PER TANK:

- 2-'DEADMAN BLOCKS CEMSTONE PRODUCT # 9557017
- 2-4" X 27' 15000 LBS. NYLON RATCHET STRAPS
- 4- STRAP PROTECTORS



COMPACT MATERIAL TO 95% STANDARD PROCTOR DENSITY (EXISTING OR IMPORTED MATERIAL) BETWEEN AND ABOVE DEADMAN BLOCKS TO TOP OF FINAL GRADE



# MONITORING AND MITIGATION

#### SEPTIC SYSTEM CLASSIFIED AS TYPE III

Should the system fail a new site for the septic system may be considered or the owner agrees to repair the septic system if it is possible. If the septic system is not repairable the homeowner agrees to disconnect the septic tanks from the septic system and use and maintain the septic tanks as holding tanks.

PINE COUNTY ZONING, MILLE LACS BAND OF OJIBWE and ENVIRONMENTAL SYSTEMS are to be notified as soon as possible about any operational problems. If a failure occurs the septic pump must be disconnected immediately and remain disconnected until all repairs are completed. A pumping contract will need to be set up with a septic maintenance contractor. A copy of all documents must be submitted to the county.

The system must be monitored for a minimum of three years. The mound system is to be inspected by the homeowner for leaks or saturated areas. Inspections are to be done every month for 36 months. Any leaks or failures in the system must be reported to the county within 24 hours.

All expenses for repair or replacement are the homeowner's responsibility.

Type III systems are not warranted by the Inspector, Designer, or Installer

1 Russell Thomas property owner of 32586 Hwy 123 Sandstone Mn.

Hereby agree that if I am the owner of the property, to accept all legal and financial responsibility for future system repair and/or replacement expenses in the event that failure of the system on the above referenced property occurs.

Owner	
•	

# University of Minnesota



#### Septic System Management Plan for Above Grade Systems

The goal of a septic system is to protect human health and the environment by properly treating wastewater before returning it to the environment. Your septic system is designed to kill harmful organisms and remove pollutants before the water is recycled back into our lakes, streams and groundwater.

This management plan will identify the operation and maintenance activities necessary to ensure long-term performance of your septic system. Some of these activities must be performed by you, the homeowner. Other tasks must be performed by a licensed septic maintainer or service provider. However, it is **YOUR** responsibility to make sure all tasks get accomplished in a timely manner.

The University of Minnesota's Septic System Owner's Guide contains additional tips and recommendations designed to extend the effective life of your system and save you money over time.

Proper septic system design, installation, operation and maintenance means safe and clean water!

Property Owner Russell Thomas	Email
Property Address 32586 Hwy 123 Sandstone Mn.	Property ID R30.0461.001
System Designer Environmental Systems	Contact Info 320-241-7036
System Installer	Contact Info
Service Provider/Maintainer	Contact Info
Permitting Authority Pine County	Contact Info
Permit #	Date Inspected

Keep this Management Plan with your Septic System Owner's Guide. The Septic System Owner's Guide includes a folder to hold maintenance records including pumping, inspection and evaluation reports. Ask your septic professional to also:

- · Attach permit information, designer drawings and as-built of your system, if they are available.
- · Keep copies of all pumping records and other maintenance and repair invoices with this document.
- Review this document with your maintenance professional at each visit; discuss any changes in product use, activities, or water-use appliances.

For a copy of the Septic System Owner's Guide, visit www.bookstores.umn.edu and search for the word "septic" or call 800-322-8642.

#### For more information see http://septic.umn.edu


Version: August 2015

# University of Minnesota

#### Septic System Management Plan for Above Grade Systems



## **Your Septic System**



Septic System	m Specifics
System Type: I OII OIII OIV* OV*  (Based on MN Rules Chapter 7080,2200 – 2400)  *Additional Management Plan required	System is subject to operating permit*  System uses UV disinfection unit*  Type of advanced treatment unit
Dwelling Type	Well Construction
Number of bedrooms: 5  System capacity/ design flow (gpd): 638  Anticipated average daily flow (gpd): 500  Comments  Business?: OY N What type?	Well depth (ft): Deep >55'  Cased well Casing depth:  Other (specify):  Distance from septic (ft):  Is the well on the design drawing?  N
Septic 1	<b>Cank</b>
□ First tank Tank volume: 2500 gallons  Does tank have two compartments?	Pump Tank gallons  Effluent Pump make/model:  Pump capacity GPM  TDH Feet of head  Alarm location
Soil Treatment	Area (STA)
Monadia Carda and Garisti as Langett Add a 110 a	Inspection ports Cleanouts Surface water diversions Additional STA not available

## University of Minnesota

# Septic System Management Plan for Above Grade Systems



## Homeowner Management Tasks

These operation and maintenance activities are your responsibility. Chart on page 6 can help track your activities.

Your toilet is not a garbage can. Do not flush anything besides human waste and toilet paper. No wet wipes, cigarette butts, disposal diapers, used medicine, feminine products or other trash!

The system and septic tanks needs to be checked every 12 months

Your service provider or pumper/maintainer should evaluate if your tank needs to be pumped more or less often.

#### Seasonally or several times per year

- · Leaks. Check (listen, look) for leaks in toilets and dripping faucets. Repair leaks promptly.
- Soil treatment area. Regularly check for wet or spongy soil around your soil treatment area. If surfaced sewage or strong odors are not corrected by pumping the tank or fixing broken caps and leaks, call your service professional. Untreated sewage may make humans and animals sick. Keep bikes, snowmobiles and other traffic off and control borrowing animals.
- Alarms. Alarms signal when there is a problem; contact your service professional any time the alarm signals.
- Lint filter. If you have a lint filter, check for lint buildup and clean when necessary. If you do not have one, consider adding one after washing machine.
- Effluent screen. If you do not have one, consider having one installed the next time the tank is cleaned along with an alarm.

#### Annually

- Water usage rate. A water meter or another device can be used to monitor your average daily water
  use. Compare your water usage rate to the design flow of your system (listed on the next page).
  Contact your septic professional if your average daily flow over the course of a month exceeds 70%
  of the design flow for your system.
- Caps. Make sure that all caps and lids are intact and in place. Inspect for damaged caps at least
  every fall. Fix or replace damaged caps before winter to help prevent freezing issues.
- Water conditioning devices. See Page 5 for a list of devices. When possible, program the recharge frequency based on water demand (gallons) rather than time (days). Recharging too frequently may negatively impact your septic system. Consider updating to demand operation if your system currently uses time,
- Review your water usage rate. Review the Water Use Appliance chart on Page 5. Discuss any major changes with your service provider or pumper/maintainer.

#### During each visit by a service provider or pumper/maintainer

- Make sure that your service professional services the tank through the manhole.
   (NOT though a 4" or 6" diameter inspection port.)
- Ask how full your tank was with sludge and scum to determine if your service interval is appropriate.
- Ask your pumper/maintainer to accomplish the tasks listed on the Professional Tasks on Page 4.

# University of Minnesota

# Septic System Management Plan for Above Grade Systems



#### **Professional Management Tasks**

These are the operation and maintenance activities that a pumper/maintainer performs to help ensure long-term performance of your system. At each visit a written report/record must be provided to homeowner.

#### Plumbing/Source of Wastewater

- Review the Water Use Appliance Chart on Page 5 with homeowner.
   Discuss any changes in water use and the impact those changes may have on the septic system.
- Review water usage rates (if available) with homeowner.

#### Septic Tank/Pump Tanks

- Manhole lid. A riser is recommended if the lid is not accessible from the ground surface. Insulate the riser cover for frost protection.
- Liquid level. Check to make sure the tank is not leaking. The liquid level should be level with the bottom of the outlet pipe. (If the water level is below the bottom of the outlet pipe, the tank may not be watertight. If the water level is higher than the bottom of the outlet pipe of the tank, the effluent screen may need cleaning, or there may be ponding in the soil treatment area.)
- · Inspection pipes. Replace damaged or missing pipes and caps.
- Baffles. Check to make sure they are in place and attached, and that inlet/outlet baffles are clear of buildup or obstructions.
- Effluent screen. Check to make sure it is in place; clean per manufacturer recommendation. Recommend retrofitted installation if one is not present.
- Alarm. Verify that the alarm works.
- Scum and sludge. Measure scum and sludge in each compartment of each septic and pump tank, pump if needed.

#### Pump

- Pump and controls. Check to make sure the pump and controls are operating correctly.
- Pump vault. Check to make sure it is in place; clean per manufacturer recommendations.
- Alarm. Verify that the alarm works.
- Drainback. Check to make sure it is draining properly.
- Event counter or elapsed time meter. Check to see if there is an event counter or elapsed time meter for the pump. If there is one or both, calculate the water usage rate and compare to the anticipated use listed on Design and Page 2. Dose Volume: \_\_\_\_\_ gallons: Pump run time: \_\_\_\_\_ Minutes

#### Soil Treatment Area

- Inspection pipes. Check to make sure they are properly capped. Replace caps and pipes that are damaged.
- Surfacing of effluent. Check for surfacing effluent or other signs of problems.
- Lateral flushing. Check lateral distribution; if cleanouts exist, flush and clean at recommended frequency.
- Vegetation Check to see that a good growth of vegetation is covering the system.

#### All other components - evaluate as listed here:

# University of Minnesota

#### Septic System Management Plan for Above Grade Systems



# Water-Use Appliances and Equipment in the Home

Appliance	Impacts on System	Management Tips
Garbage disposal	<ul> <li>Uses additional water.</li> <li>Adds solids to the tank.</li> <li>Finely-ground solids may not settle.</li> <li>Unsettled solids can exit the tank and enter the soil treatment area.</li> </ul>	<ul> <li>Use of a garbage disposal is not recommended.</li> <li>Minimize garbage disposal use. Compost instead.</li> <li>To prevent solids from exiting the tank, have your tank pumped more frequently.</li> <li>Add an effluent screen to your tank.</li> </ul>
Washing machine	<ul> <li>Washing several loads on one day uses a lot of water and may overload your system.</li> <li>Overloading your system may prevent solids from settling out in the tank. Unsettled solids can exit the tank and enter the soil treatment area.</li> </ul>	<ul> <li>Choose a front-loader or water-saving top-loader, these units use less water than older models.</li> <li>Limit the addition of extra solids to your tank by using liquid or easily biodegradable detergents. Limit use of bleach-based detergents and fabric softeners.</li> <li>Install a lint filter after the washer and an effluent screen to your tank</li> <li>Wash only full loads and think even – spread your laundry loads throughout the week.</li> </ul>
Dishwasher	<ul> <li>Powdered and/or high-phosphorus detergents can negatively impact the performance of your tank and soil treatment area.</li> <li>New models promote "no scraping". They have a garbage disposal inside.</li> </ul>	<ul> <li>Use gel detergents. Powdered detergents may add solids to the tank.</li> <li>Use detergents that are low or no-phosphorus.</li> <li>Wash only full loads.</li> <li>Scrape your dishes anyways to keep undigested solids out of your septic system.</li> </ul>
Grinder pump (in home)	Finely-ground solids may not settle.  Unsettled solids can exit the tank and enter the soil treatment area.	<ul> <li>Expand septic tank capacity by a factor of 1.5.</li> <li>Include pump monitoring in your maintenance schedule to ensure that it is working properly.</li> <li>Add an effluent screen.</li> </ul>
Large bathtub (whirlpool)	<ul> <li>Large volume of water may overload your system.</li> <li>Heavy use of bath oils and soaps can impact biological activity in your tank and soil treatment area.</li> </ul>	<ul> <li>Avoid using other water-use appliances at the same time. For example, don't wash clothes and take a bath at the same time.</li> <li>Use oils, soaps, and cleaners in the bath or shower sparingly.</li> </ul>
Clean Water Uses	Impacts on System	Management Tips
High-efficiency furnace	Drip may result in frozen pipes during cold weather.	Re-route water directly out of the house. Do not route furnace discharge to your septic system.
Water softener Iron filter Reverse osmosis	Salt in recharge water may affect system performance.     Recharge water may hydraulically overload the system.	<ul> <li>These sources produce water that is not sewage and should not go into your septic system.</li> <li>Reroute water from these sources to another outlet, such as a dry well, draintile or old drainfield.</li> </ul>
Surface drainage Footing drains	Water from these sources will overload the system and is prohibited from entering septic system.	<ul> <li>When replacing, consider using a demand-based recharge vs. a time-based recharge.</li> <li>Check valves to ensure proper operation; have unit serviced per manufacturer directions</li> </ul>

# University of Minnesota

#### Septic System Management Plan for Above Grade Systems



#### Homeowner Maintenance Log

***Bi-Annually Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  **As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take necessary corrective actions. If I have a new system, I agree to adequately protect the reserve area for future use as a soil treatment system."  Property Owner Signature:  Date	Activity			Dat	e acco	mpli	shed			
Soil treatment area check for surfacing**  Lint filter: check, clean if needed*  Effluent screen (if owner-maintained)***  Alarm**  Check annualty:  Water usage rate (maximum gpd)  Caps: inspect, replace if needed  Water use appliances – review use  Other:  Monthly  *Quarterly  ***Bi-Annually  Notes:  A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take eccessary corrective actions. If I have a new system, I agree to adequately protect the reserve reas for future use as a sell treatment system."  Property Owner Signature:  Date	Check frequently:									
Lint filter: check, clean if needed*  Effluent screen (if owner-maintained)***  Alarm**  Check annually:  Water usage rate (maximum gpd)  Caps: inspect, replace if needed  Water use appliances – review use  Other:  Monthly  **Quarterly  ***Bi-Annually  Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months . If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in his Management Plan are not met, I will promptly notify the permitting authority and take eccessary corrective actions. If I have a new system, I agree to adequately protect the reserve reas for future use as a soil treatment system.  Property Owner Signature:  Date	Leaks: check for plumbing leaks*					===				
Effluent screen (if owner-maintained)***  Alarm**  Check annually:  Water usage rate (maximum gpd)  Caps: inspect, replace if needed  Water use appliances – review use  Other:  Monthly  **Quarterly  ***Bi-Annually  Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months . If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks until mound has recovered and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  As the owner of this SSTS, I understand it is my responsibility to properly operate and maintest the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take necessary corrective actions. If I have a new system, I agree to adequately protect the reserve rea for future use as a soil treatment system."  Property Owner Signature:  Date	Soil treatment area check for surfacing**									
Check annually:  Water usage rate (maximum gpd)  Caps: inspect, replace if needed  Water use appliances – review use  Other:  Monthly  **Quarterly  ***Bi-Annually  Notes:  A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holdin tanks for a minimum of 30 days to let the mound rest and recover. If this is a recocurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain his sewage treatment system on this property, utilizing the Management Plan. If requirements in his Management Plan are not met, I will promptly notify the permitting authority and take eccessary corrective actions. If I have a new system, I agree to adequately protect the reserve rea for future use as a soil treatment system."  Property Owner Signature:  Date	Lint filter: check, clean if needed*									
Check annually:  Water usage rate (maximum gpd)  Caps: inspect, replace if needed  Water use appliances – review use  Other:  Monthly  **Bi-Annually  Notes:  A visual inspection of the mound for leaks to be done every 30 days for first 36 months . If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in his Management Plan are not met, I will promptly notify the permitting authority and take eccessary corrective actions. If I have a new system, I agree to adequately protect the reserve rea for future use as a soil treatment system."  Property Owner Signature:  Date	Effluent screen (if owner-maintained)***									
Water usage rate (maximum gpd)  Caps: inspect, replace if needed  Water use appliances – review use  Other:  *Monthly  **Quarterly  ***Bi-Annually  Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  *As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in his Management Plan are not met, I will promptly notify the permitting authority and take eccessary corrective actions. If I have a new system, I agree to adequately protect the reserve rea for future use as a soil treatment system."  Property Owner Signature:  Date	Alarm**									
Caps: inspect, replace if needed  Water use appliances – review use  Other:  *Monthly  ***Bi-Annually  Notes: grounded soggy at the base of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a recocurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  *As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take recessary corrective actions. If I have a new system, I agree to adequately protect the reserve area for future use as a soil treatment system."  Property Owner Signature:  Date	Check annually:						-			
Water use appliances – review use  Other:  *Monthly  ***Pii-Annually  Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holdin tanks for a minimum of 30 days to let the mound rest and recover. If this is a recocurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  *As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take necessary corrective actions. If I have a new system, I agree to adequately protect the reserve trea for future use as a soil treatment system."  Property Owner Signature:  Date	Water usage rate (maximum gpd)									
Other:  *Monthly  **Quarterly  *****Bi-Annually  Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  *As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take necessary corrective actions. If I have a new system, I agree to adequately protect the reserve area for future use as a soil treatment system."  Property Owner Signature:  Date	Caps: inspect, replace if needed									
*Monthly  ***Pi-Annually  Notes:  A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  This was get treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take lecessary corrective actions. If I have a new system, I agree to adequately protect the reserve trea for future use as a soil treatment system."  Property Owner Signature:  Date	Water use appliances - review use									
***Bi-Annually  A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  Was the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take necessary corrective actions. If I have a new system, I agree to adequately protect the reserve area for future use as a soil treatment system."  Property Owner Signature:  Date	Other:									
Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take necessary corrective actions. If I have a new system, I agree to adequately protect the reserve area for future use as a soil treatment system."  Property Owner Signature:  Date	Monthly							L.		
Notes: A visual inspection of the mound for leaks to be done every 30 days for first 36 months. If grounded soggy at the base of the mound the power to the septic pumped is to be shut off. A septic maintenance contractor is to be contacted to pump your septic tanks. The tanks are to be used as holding tanks until mound has recovered and dryed. The tanks should be used as holding tanks for a minimum of 30 days to let the mound rest and recover. If this is a reoccurring problem other action may be need. (As in longer rest periods, lower water usage or increase the size of the system)  As the owner of this SSTS, I understand it is my responsibility to properly operate and maintain the sewage treatment system on this property, utilizing the Management Plan. If requirements in his Management Plan are not met, I will promptly notify the permitting authority and take ecessary corrective actions. If I have a new system, I agree to adequately protect the reserve rea for future use as a soil treatment system."  Property Owner Signature:  Date	**Quarterly									
the sewage treatment system on this property, utilizing the Management Plan. If requirements in this Management Plan are not met, I will promptly notify the permitting authority and take necessary corrective actions. If I have a new system, I agree to adequately protect the reserve area for future use as a soil treatment system."  Property Owner Signature:  Date	A visual inspection of the mound for I grounded soggy at the base of the m septic maintenance contractor is to b used as holding tanks until mound ha tanks for a minimum of 30 days to let other action may be need. ( As in long	ound the personance of the contacte of the con	power to ed to pu ed and ed rest a	o the se mp you dryed. and reco	ptic purion puri	umper ic tank nks sl this i	d is to ks. The hould s a ree	be shi e tanks be use occurri	ut off. As are to d as h	be oldin blem
	the sewage treatment system on this proper this Management Plan are not met, I will p ecessary corrective actions. If I have a	rty, util. promptly in new syste	izing ti notify :	he Mana the per	gement mittin	: Plan	. If horit	requir v and	ements take	in
Management Plan Prepared By: Kevin Herwig Certification #659	Property Owner Signature:				1	Date				-
	Management Plan Prepared By: Kevin He	rwig				Certifi	ication	<b>365</b> 9	9	

©2015 Regents of the University of Minnesota. All rights reserved. The University of Minnesota is an equal opportunity educator and employer. This material is available in alternative formats upon request. Contact the Water Resources Center, 612-624-9282. The Onsite Sewage Treatment Program is delivered by the University of Minnesota Extension Service and the University of Minnesota Water Resources Center.



## Preliminary Evaluation Worksheet



1. Contact Information	v 04.02.2024
Property Owner/Client: Russell and Karen Thomas Date Co	Completed: 7/10/2024
Site Address: 32586 STATE 123 SANDSTONE MN. 55072	Project ID:
Email: russandkaren73@gmail.com	Phone: 320-372-0795
Mailing Address: same	Alt Phone:
Legal Description:	
Parcel ID: R30.0461.001 SEC: 13 TWP:	042 RNG: 020
2. Flow and General System Information	
# Adults: 2 # Children: 7  In-home business (Y/N): No If yes, describe:  Garbage Disposal/Grinder Dishwasher  Water-using devices: Sewage pump in basement Water Softener*  (check all that apply) Large Bathtub >40 gallons Iron Filter*  Clothes Washing Machine High Eff. Furnace*  * Clear water source - sho  Additional current or future uses:  Anticipated non-domestic waste:	Repair  Infinished sq.ft.:  # Teenagers:  Hot Tub*  Sump Pump*  Self-Cleaning Humidifier*  Other:  ould not go into system
The above is complete & accurate:  Client signature & date	•
B. Designer-determined Flow and Anticipated Waste Strength Information	-
Attach additional information as necessary.  Design Flow: 750 GPD Anticipated Waste Ty	vpe: Residential
	l & Grease 25 mg/L
3. Preliminary Site Information	ra orease 25 mg/L
A. Water Supply Wells	
Well Depth Casing Confining	STA Setback Source
2	
3	
4	
Additional Well Information:	



### Preliminary Evaluation Worksheet

Site within 200' of noncommunity transient well (Y/N) No Yes, source:
Site within a drinking water supply management area (Y/N) No Yes, source:
Site in Well Head Protection inner wellhead management zone (Y/N)  Yes, source:
Buried water supply pipes within 50 ft of proposed system (Y/N)
B. Site located in a shoreland district/area?  No Yes, name: N/A
Elevation of ordinary high water level: N/A ft Source: N/A
Classification: N/A Tank Setback: N/A ft. STA Setback: N/A ft.
C. Site located in a floodplain?  No Yes, Type(s): N/A
Floodplain designation/elevation (10 Year): N/A ft Source: N/A
Floodplain designation/elevation (100 Year): N/A ft Source: N/A
D. Property Line Id / Source: Owner Survey County GIS Plat Map Other:
E. ID distance of relevant setbacks on map: Water Easements Well(s)
✓ Building(s) ✓ Property Lines ☐ OHWL ☐ Other:
4. Preliminary Soil Profile Information From Web Soil Survey (attach map & description)
Map Units: c39a c22d Slope Range: %
List landforms:
Landform position(s): Shoulder
Parent materials: Outwash
Depth to Bedrock/Restrictive Feature: in Depth to Watertable: in
Septic Tank Absorption Field- At-grade:
Map Unit Ratings Septic Tank Absorption Field- Mound: Extremely Limited
Septic Tank Absorption Field- Trench:
5. Local Government Unit Information
Name of LGU: PINE COUNTY
LGU Contact:
LGU-specific setbacks:
LGU-specific design requirements:
LGU-specific installation requirements:
Notes:



#### Field Evaluation Worksheet




1. Project Information v 04.02.2024
Property Owner/Client: Russell and Karen Thomas Project ID:
Site Address: 32586 STATE 123 SANDSTONE MN. 55072 Date Completed: 7/10/2024
2. Utility and Structure Information
Utility Locations Identified Gopher State One Call # Any Private Utilities:
Locate and Verify (see Site Evaluation map)  Existing Buildings  Improvements  Easements  Setbacks
3. Site Information
Vegetation type(s): Grass Landscape position:
Percent slope: 7.0 % Slope shape: Linear, Linear Slope direction: north
Describe the flooding or run-on potential of site: May have seasonal ponding on West end
Describe the need for Type III or Type IV system: Redox and water with in 4"of surface
Note:
Proposed soil treatment area protected? (Y/N): Yes If yes, describe: staked
4. General Soils Information
Filled, Compacted, Disturbed areas (Y/N): No
If yes, describe:
Soil observations were conducted in the proposed system location (Y/N):
A soil observation in the most limiting area of the proposed system (Y/N): Yes
Number of soil observations: 4 Soil observation logs attached (Y/N): Yes
Percolation tests performed & attached (Y/N): No
5. Phase I. Reporting Information
Depth Elevation
Limiting Condition*: 0 in 97.60 ft *Most Restrictive Depth Identified from List Below
Periodically saturated soil: 0 in 97.60 ft Soil Texture: Fine Sandy Loam
Standing water: in ft Percolation Rate: min/inch
Bedrock: in ft Soil Hyd Loading Rate: 0.60 gpd/sq.ft
Benchmark Elevation: 100.0 ft Elevations and Benchmark on map? (Y/N):
Benchmark Elevation Location: Bottom of house siding
Differences between soil survey and field evaluation: Colors, redox and water features
Site evaluation issues / comments:
Anticipated construction issues: Old mound leaking area and will need time to dry septic tanks should be used as holding tanks during the drying in construction period.



#### Proposed Design Map





4	The second second	1		
Chile inskry or Mockenigh	ONSITE	SEWAGE	TREATMENT	PROGRAM

# Soil Observation Log

Project ID:

v 04.02.2024

Client:		Russell	and Kar	Russell and Karen Thomas	Se Se		Locati	Location / Address:	3258	32586 STATE 123 SANDSTONE MN. 55072	STONE MN. 55072	
oil parent n	Soil parent material(s): (Check all that apply)	eck all th	at apply	J Outwash	1		Loess TIII Alluvium Bedrock	Alluvium 🔲 B		Organic Matter Disturbed/Fill	bed/Fill	
Landscape Position:	osition:	Shoulder			Slope %:	7.0	Slope shape:	Linear,	Linear, Linear	Flooding/Run-On potential:	On potential:	Yes
Vegetation:	)	Grass		Soil survey		map units:	c39a (	c22d	Surface Ele	Surface Elevation-Relative to benchmark:	benchmark:	97.40
Date/Time o	Date/Time of Day/Weather Conditions:	r Conditio	us:	10	10am		overcast			Limiting Layer Elevation:	r Elevation:	97.15
Observatio	Observation #/Location:	1			ũ	east center		Observat	Observation Type:		Pit	
Depth (in)	Texture	Rock Frag %	Matrix	Matrix Color(s)	Mottle	Mottle Color(s)	Redox Kind(s)	Indicator(s)	Chang	I Structure-		$\prod_{i}$
4.0	Fine Sandy	r L	10YR 3/2	3/2					Pulaire	Ol auc	כחופואנפווכם	b
5	Loam	,							Glaliula	WEGK	רומטופ	
. 4-16	Fine Sandy Loam	īΩ	10YR	10YR 4/4	10YR	0YR 5/6	Concentrations	23	Blocky	Weak	Friable	
										2		
Comments:												
I hereby cert	hereby certify that I have completed this work in accordance KEVIN HERWIG	completed	this wor	k in accor	dance with	h all appli	with all applicable ordinances, rules and laws.	, rules and law	3945		ACOCIO117	
(Desi Optional Veri the periodical	(Designer/Inspector) Optional Verification: I hereby certify that this soil observation was verified according to the periodically saturated soil or bedrock at the proposed soil treatment and dispersal site.	r) by certify t or bedrock	hat this so	oposed sof	tion was ve Il treatmen	erified accost and dispe	ording to Minn. R. 7	7082.0500 subp.	(License #) 3 A. The signat	ure below represent	(License #)  (Date)  Optional Verification: I hereby certify that this soil observation was verified according to Minn. R. 7082.0500 subp. 3 A. The signature below represents an infield verification of the periodically saturated soil or bedrock at the proposed soil treatment and dispersal site.	ion of
(LGU/D	(LGU/Designer/Inspector)	tor)			(5)	(Signature)			(Cert #)	•	(Date)	
												Action and a second

4				
University or Mexicons.	ONSITE	SEWAGE	TREATMENT	PROGRAM

# Soil Observation Log

Project ID:

v 04.02.2024

Client:		Russeli	and Kar	Russell and Karen Thomas	as		Locat	Location / Address:	3258	6 STATE 123 SAND	32586 STATE 123 SANDSTONE MN. 55072	
Soil parent r	Soil parent material(s): (Check all that apply)	heck all tr	hat apply)	Outwash		Lacustrine	☐ Lacustrine ☐ Loess ☑ Till ☐ Alluvium ☐ Bedrock ☐ Organic Matter	Alluvium Be	edrock Organ	ilc Matter Disturbed/Fill	rbed/Fill	
Landscape Position:	osition:	Shoulder			Slope %:	7.0	Stope shape:	Linear,	Linear, Linear	Flooding/Run-On potential:	On potential:	Yes
Vegetation:		Grass		Soil survey		map units:	c39a (	c22d	Surface Ele	Surface Elevation-Relative to benchmark:	benchmark:	98.50
Date/Time (	Date/Time of Day/Weather Conditions:	er Conditic	suc:	7	10am		overcast			Limiting Layer Elevation:	r Elevation:	98.25
Observatic	Observation #/Location:		7		×	South center	Je.	Observat	Observation Type:		Pit	
Depth (in)	Texture	Rock	Matrix	Matrix Color(s)		Mottle Color(s)	Redox Kindle)	Indicatorics		I Structure	[Generations	
(m) index	2000	Frag. %		(6) 1000	$\neg$	(6) 10,00	(ב)חווא אסססאו	mulcacol (3)	Shape	Grade	Consistence	ce
- 5	Fine Sandy	ıc	10YR	10YR 3/2					Cranilar	Acolu		
,	Loam	,							G alluta	Weak		
4.16	Fine Sandy	Ľ	10YR	10YR 4/4	10YR	0YR 5/4	Concentrations	22	Ploclar	Acoly.	1	
	Loam	,			10YR	0YR 5/6	Concentrations	23	DIOCNY	Wear	רוומטופ	
							2					
				(2)								
									ki.			
Comments:												
I hereby ceri	ify that I have	completed	this work	k in accor	dance wil	th all appl	I hereby certify that I have completed this work in accordance with all applicable ordinances, rules and laws.	, rutes and law	ď			
×	KEVIN HERWIG		5	1	iles )	4			3945		7/10/2024	4
(Des Optional Veri the periodical	(Designer/Inspector) Verification: I hereby dically saturated soil o	or) by certify t I or bedrocl	that this so	oposed so	ition way	Signature) eritied account and dispe	ording to Minn. R ersal site.	7082.0500 subp.	(License #) 3 A. The signat	ure below represen	(Designer/Inspector)  Optional Verification: I hereby certify that this soil/observation was verified according to Minn. R. 7082.0500 subp. 3 A. The signature below represents an infield verification of the periodically saturated soil or bedrock at the proposed soil treatment and dispersal site.	tion of
2			<u>,</u>									
1/097)	(LGU/Designer/Inspector)	ctor)				(Signature)		Johnson	(Cert #)		(Date)	



# Soil Observation Log

Project ID:

v 04.02.2024

3

				-					The state of the s		6	Appropriate Proposition Committee Co
Client:		Russell	Russell and Karen Thomas	Thom:	as		Locati	Location / Address:	3258	32586 STATE 123 SANDSTONE MN. 55072	STONE MN. 5507	2
Soil parent n	Soil parent material(s): (Check all that apply)	neck all th	at apply)	✓ Outwash		acustrine [	☐ Lacustrine ☐ Loess ☑ Till ☐ Alluvium ☐ Bedrock	Alluvlum B		Organic Matter Disturbed/Fill	bed/Fill	
Landscape Position:		Shoulder			Slope %:	7.0	Slope shape:	Linear,	Linear, Linear	Flooding/Run-On potential:	On potential:	Yes
Vegetation:		Grass		Soil su	Soil survey map units:	units:	c39a c	c22d	Surface Ele	Surface Elevation-Relative to benchmark:	benchmark:	95.80
Date/Time o	Date/Time of Day/Weather Conditions:	r Condition	ns:	10	10am		overcast			Limiting Layer Elevation:	r Elevation:	95.50
Observatio	Observation #/Location:	3			NC	North center	<u>.</u>	Observat	Observation Type:		Pit	
Denth (in)	Toyture	Rock	Matrix	Matrix Color(s)	Mottle	Color(e)	Mottle Color(s) Bedox Kind(s)	Indicatories		Structure	'el	
nebai (iii)	ובערמוב	Frag. %	אומרו זע	(6) 10107	MOLLIC	(e) 10100	" Nedox Milia(s)	IIIdicatol (s)	Shape	Grade	Consistence	nce
-	Organic		10YR 2/2	2/2				E	Granular	Weak	Friahle	
	560									Heav	300	1
7,5	Very Fine	0	10YR 2/2	2/2	10YR 4/6	4/6	Concentrations	T5	Granular	Wool		
<u> </u>	Sandy Loam	•			10YR 6/2	6/2	Depletions	£	Gi aliutai	Wedn	רו ומוני	
п С	Loamy Fine	•	10YR 5/2	5/2	10YR 4/6	4/6	Concentrations	52	Dieno	14/ And F	, r	
2	Sand	-							DECENS	Wean	וממוני	16
										-031		
Comments:	Comments: WATER @ 3"											
I hereby cert	I hereby certify that I have completed this work in accordance	completed	this work	in accor	dance with	ildpplie r	with all applicable ordinances, rules and laws.	, rules and law	Š			
<u>~</u>	KEVIN HERWIG		V	1	1	1100	1		3945		7/10/2024	
(Des	(Designer/Inspector)	5	/	1		Signature			(License #)		(Date)	
Optional Veri the periodical	Optional Verification: I hereby certify that this soil observation was verified according to I the periodically saturated soil or bedrock at the proposed soil treatment and dispersal site.	by certify to or bedrock	that this straight at the pr	il observa	ation was wal	erified act	ording to Minn. R. ersal site.	7082.0500 subp.	3 A. The signat	Optional Verification: I hereby certify that this soil observation was verified according to Minn. R. 7082.0500 subp. 3 A. The signature below represents an infield verification of the periodically saturated soil or bedrock at the proposed soil treatment and dispersal site.	ts an infield verific	ation of
			-									
(LGU/D	(LGU/Designer/Inspector)	tor)			<u></u>	(Signature)			(Cert #)		(Date)	



## Design Summary Page



1. PROJECT INFORMATIO	N	10.50		v 04.02.2024				
Property Owner/Client:	Russell and Karen The	omas		Project ID:	7			
Site Address:	32586 STATE 123 SAN	DSTONE MN. 5507	2	Date: 07/10/24	Ī			
Email Address:	russandkaren73@gma	il.com	1000	Phone: 320-372-0795	Ī			
2. DESIGN FLOW & WAST	E STRENGTH							
I	Design Flow: 750	GPD	Anticipated	Waste Type: Residential	٦			
	BOD: 170	mg/L TSS:	mg/L C	oil & Grease: 25 mg/l	L			
Treat	ment Level: C	Select Treatment Le	 vel C for residential s					
3. HOLDING TANK SIZING	Holding Tank Sizi	ng: see 7080.2290		111111111111111111111111111111111111111				
Code Minimum Holding Tar	nk Capacity:	Gailons with	Tanks	s or Compartments				
Recommended Holding Tar	nk Capacity:	Gallons with	Tanks	s or Compartments				
The holding tank(s) will	be:	Existing tank (	reuse requires a tank i	ntegrity assessment				
Type of High Level Alarm:								
(Alarm Set ® 75%	tank capacity measured	from inlet to bott	:om)					
Comments:				200	7			
4. SEPTIC TANK SIZING	Sizing: See 7080.	1930		****	_			
A. Residential dwellings:	***************************************		454464444444444444444444444444444444444	***************************************	П			
Number of Bedrooms (Residential): 5								
Code Minimum Septic Tar	k Capacity: 1500	Gallons with	1 Tanks	or Compartments				
Recommended Septic Tar	k Capacity: 2500	Gallons with	2 Tanks	or Compartments				
The septic tank(s) will t	e: All New	Existing tank r	euse requires a tank ir	ntegrity assessment				
Comments:	Tal	e anchoring mayb	e needed					
Effluent Screen & Alarm (	Y/N): Yes	Model/Type:	POLY	LOK PL-122	1			
B. Other Establishments:	(#4) (#4) (#4) (#4) (#4) (#4) (#4) (#4)		8 bol ståd i de skonet politika byd propi propi predikter					
1	eceived by:		GPD x	Days Hyd. Retention Time				
7080 Minimum Septic Tan		Gallons with		or Compartments				
-				-				
Designed Septic Tan				or Compartments				
The septic tank(s) will b	e:	Existing t	ank reuse requires a to	ank integrity assessment				
Comments:	van			-				
Effluent Screen & Alarm ( * Other Establishme	Y/N): ents Require Department of L	Model/Type: abor and Industry App	proval and Inspection	for Building Sewer *				
-					$\vdash$			



## Design Summary Page



Soil Treatment Dosing Tank Pump Tank Capacity (7080 Minimum): 750 Gal Pump Tank Capacity (Designed): 2000 Gal Pump Req: 48.0 GPM Total Head 20.3 ft Pump Tank Capacity (Designed): Gal Pump Req: 48.0 GPM Total Head 20.3 ft Pump Tank Capacity (Designed): Gal Pump Req: 48.0 GPM Total Head 20.3 ft Pump Pank Capacity (Designed): Gal Pump Req: 48.0 GPM Total Head 70 Dose Vol: 187.0 gal 5 Supply Pipe Dia. 1 Dose Vol: Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Req: GPM Total Head 70 Pump Pank Capacity (Designed): Gal Pump Tank Capacity (Designed): GPM Total Head 71 Pump Pank Capacity (Designed): GPM Total Pank Capacity (Designed): GPM Total Pank Capacit	5. PUMP TANK SIZING Sizing: see 7080.2100	
Pump Tank Capacity (7080 Minimum): 750 Gat Pump Tank Capacity (Designed): Gat Pump Tank Capacity (Designed): 2000 Gat Pump Req: 48.0 GPM Total Head 20.3 ft Pump Req: 48.0 GPM Total Head 20.3 ft Pump Req: GPM Total Head ft Pump		
Pump Tank Capacity (Designed): 2000 Gal Pump Tank Capacity (Designed): Gal Pump Req: 48.0 GPM Total Head 20.3 ft Pump Req: 48.0 GPM Total Head 20.3 ft Pump Req: 48.0 GPM Total Head 20.3 ft Pump Req: 48.0 GPM Total Head ft Pump Req: 48.0 GPM Total Head 20.3 ft Pump Req: 48.0 GPM Total Head ft Register Manual Pump Reg: 48.0 GPM Total Head ft Register Manual Register Register Depth Manual Register Manual Register Manual Register Re		
Pump Req: 48.0 GPM Total Head 20.3 ft Pump Req: GPM Total Head ft Supply Pipe Dia. 2.00 in Dose Vot: 187.0 gal Supply Pipe Dia. in Dose Vot: Gal Flow measurement device must be incorporated for any system with a pump *  6. SYSTEM AND DISTRIBUTION TYPE Project ID:  Soil Treatment Type: Mound Distribution Type: Pressure Distribution-Level Benchmark: 100.00 ft Benchmark Location: Bottom of house siding MPCA System Type: Type III Distribution Media: Rock  Type III/IV/V Details: timed  7. SITE EVALUATION SUMMARY:  Describe Limiting Condition: Redoximorphic Features/Saturated Soils  Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:  Limiting Condition: 0.0 inches 0.00 ft 97.60 ft System compliance.  Limiting Condition: 3.6 inches 0.00 ft Pr. Media Bottom Elevation OK  This is the measuman depth to the bottom of the distribution media for resulted separation. Regative Depth (If) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note: Comments:  E. Measured Land Slope: 7.0 % Note: Comments:  Dispersal Area Sq.ft Sidewall Depth in Trench Width ft Designed Trench Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth In Maximum Bed Depth In Dispersal Area Sq.ft Sidewall Depth In Maximum Bed Depth In Sq.ft Sidewall Depth In Sq.		Pump Tank Capacity (7080 Minimum): Gal
Supply Pipe Dia. 2.00 in Dose Vol: 187.0 gal Supply Pipe Dia. in Dose Vol: Gal  Flow measurement device must be incorporated for any system with a pump*  6. SYSTEM AND DISTRIBUTION TYPE Project ID:  Soil Treatment Type: Mound Distribution Type: Project ID:  Soil Treatment Type: Mound Distribution Type: Project ID:  Soil Treatment Type: Mound Distribution Media: Rock  MPCA System Type: Type III Distribution Media: Rock  Type III/IV/V Details: timed  7. SITE EVALUATION SUMMARY:  Describe Limiting Condition: Redoximorphic Features/Saturated Soils  Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:  Limiting Condition: 0.0.0 inches 0.00 ft 97.60 ft Elevations are critical for system compliance.  Minimum Req'd Separation: 36 inches 3.00 ft Elevation  Distribution Media Bottom* Mound inches -3.00 ft 100.60 ft Media Bottom Elevation OK  This is the maximum depth to the bottom of the distribution media for resulted separation. Negative begin fit) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/rt² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area 39.ft Sidewall Depth in Trench Wridth ft Designed Trench Depth in Bed: Dispersal Area 39.ft Sidewall Depth in Maximum Bed Depth in Bed: Dispersal Area 39.ft Sidewall Depth in Maximum Bed Depth in Bed: Dispersal Area 39.ft Sidewall Depth in Maximum Bed Depth in In Dispersal Area 39.ft Sidewall Depth In In Maximum Bed Depth In In In Maximum Bed Depth In	Pump Tank Capacity (Designed): 2000 Gal	Pump Tank Capacity (Designed): Gal
* Flow measurement device must be incorporated for any system with a pump *  6. SYSTEM AND DISTRIBUTION TYPE Project ID:  Soll Treatment Type:   Mound   Distribution Type:   Pressure Distribution-Level   Elevation Benchmark:   100.00   ft   Benchmark Location:   Bottom of house siding   MPCA System Type:   Type III   Distribution Media:   Rock   Type IIII/IV/V Details:   timed   Type III   Distribution Media:   Rock   Type IIII/IV/V Details:   timed   Type III   Distribution Media:   Rock   Type IIII/IV/V Details:   timed   Type III   Distribution Media:   Rock   Type III/IV/V Details:   timed   Type III   Distribution Media:   Rock   Type III/IV/V Details:   timed   Type III   Distribution Media:   Rock   Type III/IV/V Details:   timed   Type III   Distribution Media Detail   Type III   Type III   Distribution Media Detail   Type III   Depth   Depth   Elevation   System compliance.   Layers with >35% Rock Fragments? (yes/no)   No   If yes, describe below: % rock and layer thickness, amount of soll credit and any additional information for addressing the rock fragments in this design.  Note:   Depth	Pump Req: 48.0 GPM Total Head 20.3 ft	Pump Req: GPM Total Hèad ft
Soft Treatment Type:	°	[ July 1   J
Distribution Type:   Mound   Distribution Type:   Pressure Distribution—Level		ncorporated for any system with a pump *
Elevation Benchmark: 100.00 ft Benchmark Location: Rock  MPCA System Type: Type III Distribution Media: Rock  Type III/IV/V Details: timed  7. SITE EVALUATION SUMMARY:  Describe Limiting Condition: Redoximorphic Features/Saturated Soils  Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:  Depth Depth Elevation  Limiting Condition: 0.0.0 inches 0.00 ft 97.60 ft System compliance.  Minimum Req'd Separation: 36 inches 3.00 ft Elevation  Distribution Media Bottom*: Mound inches 3.00 ft Elevation  Distribution Media Bottom*: Mound inches 3.00 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench: Dispersal Area Sq.ft Sidewall Depth ft Designed Trench Depth in Bed: Dispersal Area Sq.ft Sidewall Depth ft Designed Trench Depth in Maximum Bed Depth in Bed: Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Maximum Bed Depth in Bed: Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Maximum Bed Depth in Bed: Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Maximum Bed Depth in Bed: Dispersal Area Sq.ft Sidewall Depth In Maximum Bed Depth In Sq. Maximum Bed Depth In Maximum Bed Depth In Sq. Maximum Bed Depth In In	6. SYSTEM AND DISTRIBUTION TYPE	Project ID:
MPCA System Type: Type III Distribution Media: Rock  Type III/IV/V Details: timed  7. SITE EVALUATION SUMMARY:  Describe Limiting Condition: Redoximorphic Features/Saturated Soils  Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:  Limiting Condition: 0.0 inches 0.00 ft 97.60 ft Elevations are critical for system compliance.  Limiting Condition: 0.0 inches 0.00 ft 97.60 ft Elevation are critical for system compliance.  Distribution Media Bottom*: Mound inches -3.00 ft Elevation on the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MP!  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.,ft Sidewall Depth in Trench Width ft Trench:  Contour Loading Rate ft No. of Trenches Code Max. Trench Depth in Special Minimum Length ft Designed Trench Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in Dispersal Area sq.,ft Sidewall Depth in Disp	Soil Treatment Type: Mound	Distribution Type: Pressure Distribution-Level
Type III/IV/V Details: timed  7. SITE EVALUATION SUMMARY:  Describe Limiting Condition: Redoximorphic Features/Saturated Soils  Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:  Depth Depth Depth Elevation  Limiting Condition: 0.00 inches 0.00 ft 97.60 ft Elevations are critical for system compliance.  Minimum Req'd Separation: 36 inches 3.00 ft Elevation  Distribution Media Bottom*: Mound inches -3.00 ft Media Bottom Elevation oK  This is the maximum depth to the bottom of the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MAP!  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area Sq.ft Sidewall Depth in Trench Width ft Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in Contour Loading Rate ft Minimum Length ft Designed Trench Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Dispersal Area Sq.ft Sidewall Depth In Dispersal Area Sq.ft Sidewall Depth In Designed Trench Depth In Dispersal Area Sq.ft Sidewall Depth In Designed Trench Depth In Dispersal Area Sq.ft Sidewall Depth In Designed Trench Depth In Dispersal Area Sq.ft Sidewall Depth In Designed Trench Depth In Dispersal Area Sq.ft Sidewall Depth In Designed Trench Depth In Dispersal Area Sq.ft Sidewall Depth	Elevation Benchmark: 100.00 ft Ben	nchmark Location: Bottom of house siding
Describe Limiting Condition: Redoximorphic Features/Saturated Soils  Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:    Depth	MPCA System Type: Type III	Distribution Media: Rock
Describe Limiting Condition: Redoximorphic Features/Saturated Soils  Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:    Depth	Type III/IV/V Details: timed	
Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:    Depth	7. SITE EVALUATION SUMMARY:	
Layers with >35% Rock Fragments? (yes/no) No If yes, describe below: % rock and layer thickness, amount of soil credit and any additional information for addressing the rock fragments in this design.  Note:    Depth	Describe Limiting Condition: Redovimorphic Features (S.	turated Coils
soil credit and any additional information for addressing the rock fragments in this design.  Note:    Depth		
Depth   Depth   Depth   Elevation   System compliance.		es, describe below: % rock and layer thickness, amount of
Limiting Condition:  Depth Limiting Condition:  Depth Limiting Condition:  Depth Limiting Condition:  Distribution Media Bottom*:  Mound inches  Jistribution Media Bottom*:  Mound inches  Journal of the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation:  A. Soil Texture:  Fine Sandy Loam  B. Soil Hyd. Loading Rate:  D. Contour Loading Rate:  Limiting Condition:  Mound Minimum Sand Depth (ft) requires a mound.  Mound Minimum Sand Depth:  MPI  D. Contour Loading Rate:  Limiting Condition:  Mound Minimum Sand Depth (ft) requires a mound.  Mound Minimum Sand Depth:  MPI  D. Contour Loading Rate:  Limiting Condition:  Mound Minimum Sand Depth (ft) requires a mound.  Mound Minimum Sand Depth:  MPI  D. Contour Loading Rate:  Limiting Condition:  Mound Minimum Sand Depth:  MPI  D. Contour Loading Rate:  Note:  Limiting Condition:  Soil Texture:  Fine Sandy Loam  Note:  Limiting Condition:  Mound Minimum Sand Depth:  MPI  D. Contour Loading Rate:  Note:  Limiting Condition:  Mound Minimum Sand Depth:  MPI  D. Contour Loading Rate:  Soil Texture:  Note:  Limiting Condition:  Media Bottom Elevation ox  Media Bottom Elevation ox  Note:  MPI  D. Contour Loading Rate:  Soil Texture:  Note:  Limiting Condition:  Soil Texture:  Note:  Limiting Condition:  Mound Minimum Sand Depth:  Mpi  Mound Minimum Sand Depth:  Mpi  Trench Width  ft  Code Max. Trench Depth  In  Contour Loading Rate  Dispersal Area  Soil Texture:  Dispersal Area  Soil Texture:  Soil Minimum Length  Mound Minimum Sand Depth  In  Mound Minimum Sand Depth:  Mpi  Mound Minimum Sand Depth (in the Sequence Sand Sand Sand Sand Sand Sand Sand Sand		g the rock fragments in this design.
Limiting Condition: 0.0 inches 0.00 ft 97.60 ft Elevations are critical for system compliance.  Minimum Req'd Separation: 36 inches 3.00 ft Elevation  Distribution Media Bottom*: Mound inches -3.00 ft 100.60 ft Media Bottom Elevation 0K  This is the maximum depth to the bottom of the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY   Trench: Dispersal Area Sq.ft Sidewall Depth in Trench Width ft Total Lineal Feet ft No. of Trenches Code Max. Trench Depth in Contour Loading Rate ft Minimum Length ft Designed Trench Depth in Ped Width  Bed: Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Ped Width In Maximum Bed Depth In Designed Trench Depth In Designed Tren		
Limiting Condition: 0.0 inches 0.00 ft 97.60 ft Elevations are critical for system compliance.  Minimum Req'd Separation: 36 inches 3.00 ft Elevation  Distribution Media Bottom*: Mound inches -3.00 ft 100.60 ft Media Bottom Elevation 0K  This is the maximum depth to the bottom of the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY   Trench: Dispersal Area Sq.ft Sidewall Depth in Trench Width ft Total Lineal Feet ft No. of Trenches Code Max. Trench Depth in Contour Loading Rate ft Minimum Length ft Designed Trench Depth in Ped Width  Bed: Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in Ped Width In Maximum Bed Depth In Designed Trench Depth In Designed Tren	Depth Dept	h Flevation
Minimum Req'd Separation: 36 inches 3.00 ft Elevation  Distribution Media Bottom*: Mound inches -3.00 ft 100.60 ft Media Bottom Elevation OK  This is the maximum depth to the bottom of the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.,ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate sq.,ft Sidewall Depth ft Designed Trench Depth in  Bed:  Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in  Park Width ft Designed Trench Depth in  Bed:  Dispersal Area sq.,ft Sidewall Depth in Maximum Bed Depth in		
Distribution Media Bottom*: Mound inches -3.00 ft 100.60 ft Media Bottom Elevation OK  This is the maximum depth to the bottom of the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  S. SOIL TREATMENT AREA DESIGN SUMMARY   Trench:  Dispersal Area Sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in  Part Width Ft Designed Trench Depth in  Dispersal Area Sq.ft Sidewall Depth in Maximum Bed Depth in		system compliance.
This is the maximum depth to the bottom of the distribution media for required separation. Negative Depth (ft) requires a mound.  Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in		Elevation
Designed Distribution Bottom Elevation: 100.60 ft Mound Minimum Sand Depth: 36 inches  A. Soil Texture: Fine Sandy Loam  B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area Sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in		
B. Soil Hyd. Loading Rate: 0.60 GPD/ft² C: Percolation Rate: MPI  D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in  Ped Width Ped Middle Sq.ft Sidewall Depth in Maximum Bed Depth in	· - · · · · · · · · · · · · · · · · · ·	
D. Contour Loading Rate: 12.0 Note:  E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.ft Sidewall Depth in Trench Width ft Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in Contour Loading Rate ft Minimum Length ft Designed Trench Depth in Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in Part Length ft Designed Trench Depth in Designed Trench Depth in Maximum Bed Depth in Maximum Bed Depth in Designed Trench Depth In Desi	A. Soil Texture: Fine Sandy Loam	
E. Measured Land Slope: 7.0 % Note:  Comments:  8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	B. Soil Hyd. Loading Rate: 0.60 GPD/ft <sup>2</sup> C:	Percolation Rate: MPI
8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	D. Contour Loading Rate: 12.0 Note:	
8. SOIL TREATMENT AREA DESIGN SUMMARY  Trench:  Dispersal Area sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	E. Measured Land Slope: 7.0 % Note:	
Trench:  Dispersal Area sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	Comments:	
Dispersal Area sq.ft Sidewall Depth in Trench Width ft  Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	8. SOIL TREATMENT AREA DESIGN SUMMARY	
Total Lineal Feet ft: No. of Trenches Code Max. Trench Depth in  Contour Loading Rate ft Minimum Length ft Designed Trench Depth in  Bed:  Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	Trench:	
Contour Loading Rate   ft   Minimum Length   ft   Designed Trench Depth   in    Bed: Dispersal Area   sq.ft   Sidewall Depth   in   Maximum Bed Depth   in    Pod Midth   St.   Pod Length   Pod Length   St.   Pod Length   St.   Pod Length   Po	Dispersal Area sq.ft Sidewall Depth	in Trench Width ft
Bed: Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	Total Lineal Feet ft: No. of Trenches	Code Max. Trench Depth in
Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	Contour Loading Rate ft Minimum Length	ft Designed Trench Depth in
Dispersal Area sq.ft Sidewall Depth in Maximum Bed Depth in	Bed:	
Pod Width 64 Pod Loveth 6		in Maximum Bed Depth in



## Design Summary Page



Project ID:												
Mound:							rojec	LID.			100	
Dis	persal Area	850.0	sq.ft		Bed Length	85.0	ft		Вес	i Widtl	10.0	]ft
Absor	ption Width	20.0	ft	Cle	ean Sand Lift	3.0	ft		Berm Width	(0-1%	)	ft
Upslope I	Berm Width	12.4	]ft	Dow	nslope Berm	21.7	ft	En	dslope Berm	ı Widti	17.1	ft
Total Sys	tem Length	119.2	]ft	S	ystem Width	44.1	ft	Co	ntour Loadir	ng Rate	12.0	gai/ft
At-Grade:												
Dis	persal Area		sq.ft		Bed Length		ft		Bed	<b>Width</b>		]ft
Up	slope Berm		]ft	Dow	nslope Berm		]ft		Finished	Height	:	ft
Sys	tem Length		]ft	End	dslope Berm		]ft		System	Width		ft
Level & Equ	al Pressure	Distributio	n Soil '	Treat	ment Area							
No. o	of Laterals	3	]	Later	al Diameter	2.00	]in		Lateral Spa	acing	3.2	]ft
Perforati	ion Spacing	3.0	ft	Per	foration Dia	meter 7.	/32	]in	Drainback Vo	olume	7.8	gal
Min Do	ose Volume	169.3	gal M	lax Do	se Volume	187.5	gal	Tot	al Dosing Vo	lume	194.8	gal
Non-Level a	nd Unequa	Pressure D	istribu	ition :	Soil Treatm	ent Area						
	Elevation	Pipe Size	Pip : Volu		Pipe	Perf Size	Sp	acing	Spacing		Minimum D	ose
	(ft)	(in)	(gal/		Length (ft)	(in)		(ft)	(in)		Volume	gal
Lateral 1										1	Maximum D	i_
Lateral 2											Volume	,03E
Lateral 3												gal
Lateral 4		241									Total Dosin	g
Lateral 5				-		*6.1	-				Volume	,
Lateral o					- Marie					1		gal
9. Organi	c Loading a	nd Addition	nal Info	for l	ISW or Type	e IV/V Desig	n -	See Or	ganic Loadi	ng tab		
Organic Load	ding to Soil	Treatment	(Based	on V	Vaste Strens	th Data and	d Org	anic Lo	oading Desig	รูก)		
A. Organic	c Loading Ba	ased on:			B. Mi	numum requ	uired	area		sq.ft		
Technology :	Strength Re	duction (T	etmen	t Lev	el or HSW)					7.1		
A. Starting	g Waste Stre	ength [		William		Tre	eatm	ent des	inged to me	et:		
Pret	reatment T	echnology:							*Must	Meet	or Exceed T	arget
		Model:				Units:	*Must Meet or Exceed Target Level					
Dis	sinfection T	echnology:							*Requ	ired fo	or Levels A 8	ÈВ
		Model:				Units:			=======================================			
10. Comme	ents/Specia	l Design Co	nsidera	tions	:							NAC
I hereby	certify that	t I have com	pleted	this	work in aced	rdance with	alla	applicat	ole ordinanc	es, rul	es and laws.	
KEY	VIN HERWIG			Ter	4//h	uns			3945		7/10/202	24




# Mound Design Worksheet ≥1% Slope



1. SYSTEM SIZING:	Proje	ct ID:				v (	4.02.2024
A. Design Flow:	750	GPD		TA:	LE X	hi ani ji	
B. Soil Loading Rate:	0.60	GPD/sqft		OR DETERM	INIKE BOT	OM ABSORE	TION AREA
C. Depth to Limiting Condition		ft			Levelo	Treatment La	vef A, A-2, B,
D. Percent Land Slope:	7.0	%			Mound Absorption	Absorption Area Loading	Mound Absorption
E. Media (Sand) Loading Rate:	1.2	GPD/sqft			e ente	(gpti/ft <sup>2</sup> )	Retio
F. Mound Absorption Ratio:	2.00		<0.1 0.1 to 5	1.2	1	-	1
			0.1 to 5 (fine sand and loamy fine earld)	0.6	2	1.6	1.6
	En la laction de la company		6 to 15	0.78	1.5	1	1.6
Barrie and Company		98,31	16 to 30	0.6	2	0.78	2
A 19 CALL CONTRACTOR OF THE PARTY OF THE PAR		11001111	31 to 45	0.6	2.4	0.78	2
≤60mpf 1.0, 1.3, 2.0, 2.4, 2.	A DECEMBER OF THE PROPERTY OF	******	46 to 60	0.45	2.6	0.6	2.6
1.0, 1.3, 2.0, 2.4, 2.	6 → ≤12		61 to 120	- 1	5	0.3	6.3
61-120 mpi OR 5.0	→ <u>s12</u>	7	>120		-		
<b>→</b>	- I	<b>⊣</b> •	Systems with th	ese value	are not	Type I syst	ems
≥ 120 mpi* >5.0*	→ ≤6*	1	Contour Loadin	ng Rate (li	near load	ing rate) i	s a
				commend			
2. DISPERSAL MEDIA SIZING							
A. Hydraulic Absorption Required Bot	tom Area: De	sign Flow	(1A) + Design A	hedia Load	ling Rate(	1E)	
750 GPD ÷		GPD/sqft	-	sq.ft		•	
Optional Upsizing of Dispersal Media	Area	******************		, e é e s s s s s s s s s s s s s s s s s	*******************************	****************	
B. Larger Bed Area Size or Organic Sizing of Bed Area 850.0 sq.ft							
[see organic loading she	et(2G)]		030.0	Jaq.ic			
	************************************	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	***************************************	*******************************	4444488184848488886644		*************
C. Designed Dispersal Media Area:	850.0	iq.ft <i>Lar</i>	ger of 2A or 2B				- 1
D. Enter Dispersal Bed Width:	10.0	t Car	not exceed 10	feet			
E. Calculate Contour Loading Rate: B	ed Width(2D)	X Design	Media Loading I	Rate(1E)			- 1
10.0 ft X 1.2			12.0 gal/f	. ,	'an mad		.
						ceed Tabl	e 1
F. Calculate Minimum Dispersal Bed L		sal Bed A	rea(2C) ÷ Bed \	Width(2D)			- 1
850 sqft + 10.	0   ft =	85.0	ft				- 1
If a larger dispersal media Ler	gth is desired	, enter L	ength(ft):	ft	:		
. ABSORPTION AREA SIZING					_		
A. Calculate Absorption Width: Bed W	idth/2D) V II	ound Abre	embine Debis (4F				
10.0 ft X 2.0		20.0	ft	)			
			_				1
B. For slopes >1%, the Absorption Wid					of the Bed	d.	
Calculate Downslope Absorption Wi	dth: Absorpti	on Width	(3A) - Bed Widt	h(2D)			- 1
,	20.0 ft	t -	10.0 ft =	10.0	ft		
-							

4.	DISTRIBUTION MEDIA: Project ID:
	Select Dispersal Media: Rock Enter Either 4A or 4B
A.	Rock Depth Below Distribution Pipe
	6 in
,	Posistaved Media
B.	Registered Media Check registered product
	Registered Media Depth in information for specific application details and design
	Specific Media Comments:
5.	MOUND SIZING Project ID:
A.	Clean Sand Lift: Required Separation - Depth to Limiting Condition = Clean Sand Lift (1 ft minimum)
	3.00 ft - ft = 3.00 ft Design Sand Lift (optional): 3 ft
В.	Upslope Height: Clean Sand Lift(5A) + Depth of Media(4AorB) +Depth to Cover Pipe+ Depth of Cover (1 ft)
	3.00 ft + 0.50 ft + 0.50 ft + 1.00 ft = 5.00 ft
SAME.	
Ups	Ratio 3:1 3.00 2.91 2.83 2.75 2.68 2.61 2.54 2.48 2.42 2.36 2.31 2.26 2.21 Ratio 3:1 3:00 3:57 3:57 3:45 3:33 3:23 3:12 3:03 2:34 2:36 2:37 2:78 2:70
С.	Select Upslope Berm Multiplier (based on land slope): 2.48
	Calculate Upslope Berm Width: Multiplier (5C) X Upslope Mound Height (5B)
	2.49
E.	Calculate Drop in Elevation Under Bed: Bed Width(2D) X Land Slope(1D) ÷ 100 = Drop (ft)
	10.00 ft X 7.0 % ÷ 100 = 0.70 ft
F. (	Calculate Downslope Mound Height: Upslope Height(5B) + Drop in Elevation(5E)
	5.00   ft + 0.70   ft = 5.70   ft
	Biologica 22
Do	ownsione 3:1 3.00 3.09 3.19 3.30 3.41 3.53 3.66 3.80 3.95 4.11 4.29 4.48 4.69
	rm Ratio 20 2000 2 17 2 25 2 26 2 20 2 26 2 26 2 2 2 2 2 2 2 2 2 2
	Select Downslope Berm Multiplier (based on land slope): 3.80
H. (	Calculate Downslope Berm Width: Downslope Multiplier(5G) X Downslope Height (5F)
	3.80 x 5.70 ft = 21.66 ft
1. (	Calculate Minimum Berm to Cover Absorption Area: Downslope Absorption Width(3B) + 4 feet
	10.00 ft + 4.00 ft = 14.00 ft
J. [	Design Downslope Berm = greater of 5H and 5I: 21.66 ft
<b>K.</b> S	select Endslope Berm Multiplier: 3.0 (usually 3.0 or 4.0)
L. C	Calculate Endslope Berm Width = Endslope Berm Multiplier(5K) X Downslope Mound Height(5F)
	3.00 X 5.7 ft = 17.10 ft
M. C	alculate Mound Width: Upslope Berm Width(5D) + Bed Width(2D) + Downslope Berm Width(5J)
	12.40 ft + 10.00 ft + 21.66 ft = 44.06 ft
N. C	alculate Mound Length: Endslope Berm Width (5L) + Bed Length(2F) + Endslope Berm Width(5L)
	17.10 ft + 85.00 ft + 17.10 ft = 119.20 ft





# **Estimated Mound Materials Worksheet**

Mound to be constructed to dimensions in design. This is an estimate of materials needed.
Individual construction practices may vary quantities.
Project ID: v 04.02.2024
A. Rock Volume: (Rock Below Pipe + Rock to cover pipe (pipe outside dia + -2 inch)) X Bed Length X Bed Width = Volume
( 6 in + 5.0 in ) ÷ 12 X 85.0 ft X 10.0 ft = 779.2 cu.ft
Divide cu.ft by 27 cu.ft/cu.yd to calculate cubic yards: 779.2 cu.ft ÷ 27 = 28.9 cu.yd
Add 30% for constructability: 28.9 cu.yd X 1.3 = 37.5 cu.yd
B. Calculate Clean Sand Volume:
Volume Under Rock bed: Average Sand Depth x Media Width x Media Length = cubic feet
3.4 ft X 10.0 ft X 85 ft = 2848 cu.ft
For a Mound on a slope from 0-1%
Volume from Length = ((Upslope Mound Height - 1) X Absorption Width Beyond Bed X Media Bed Length)
ft - 1) X X ft =
Volume from Width = ((Upslope Mound Height - 1) X Absorption Width Beyond Bed X Media Bed Width)
ft - 1) X X ft =
Total Clean Sand Volume : Volume from Length + Volume from Width + Volume Under Media
cu.ft + cu.ft = cu.ft
For a Mound on a slope greater than 1%
Upslope Volume: ((Upslope Mound Height - 1) x 3 x Bed Length) + 2 = cubic feet
(( 5.0 ft - 1) X 3.0 ft X 85.0 ) ÷ 2 = 510.0 cu.ft
Downslope Volume: ((Downslope Height - 1) x Downslope Absorption Width x Media Length) + 2 = cubic feet
(( 5.7 ft - 1) X 10.0 ft X 85.0 ) ÷ 2 = 1997.5 cu.ft
Endslope Volume: (Downslope Mound Height - 1) x 3 x Media Width = cubic feet
( 5.7 ft - 1) X 3.0 ft X 10.0 ft = 141.0 cu.ft
Total Clean Sand Volume : Upslope Volume + Downslope Volume + Endslope Volume + Volume Under Media
510.0 cu.ft + 1997.5 cu.ft + 141.0 cu.ft + 2847.5 cu.ft = 5496.0 cu.ft
Divide cu.ft by 27 cu.ft/cu.yd to calculate cubic yards: 5496.0 cu.ft ÷ 27 = 203.6 cu.yd
Add 30% for constructability:  203.6 cu.yd X 1.3 = 264.6 cu.yd
C. Calculate Sandy Berm Volume:
Total Berm Volume (approx.): ((Avg. Mound Height - 0.5 ft topsoil) x Mound Width x Mound Length) + 2
( 5.4 - 0.5 )ft X 44.1   ft X 119.2   ) ÷ 2 = 12736.0   cu.ft
Total Mound Volume - Clean Sand volume -Rock Volume = cubic feet
12736.0 cu.ft - 5496.0 cu.ft - 779.2 cu.ft = 6460.8 cu.ft
Divide cu.ft by 27 cu.ft/cu.yd to calculate cubic yards: 6460.8 cu.ft + 27 = 239.3 cu.yd
Add 30% for constructability: $239.3$ yd <sup>3</sup> x 1.3 = $311.1$ cu.yd
D. Calculate Topsoil Material Volume: Total Mound Width X Total Mound Length X .5 ft
44.1 ft X 119.2 ft X 0.5 ft = 2626.0 cu.ft
Divide cu.ft by 27 cu.ft/cu.yd to calculate cubic yards: 2626.0 cu.ft ÷ 27 = 97.3 cu.yd
Add 30% for constructability: 97.3 cu.yd X 1.3 = 126.4 cu.yd
Cu.yu



# Pressure Distribution Design Worksheet




PRO	DGRAM				Jesign	I WOLF	csneet					
						Projec	t ID:				,	04.02.202
1.	Media Bed Wid	th:				10.	0 ft					
2.	Media Bed Leng	gth:				85.	0 ft					
3.	Minimum Numb	er of La	terals in	ı system	/zone =	Rounde	d up number of	[(Media	Bed Wid	lth(1.) -	4) ÷ 31	+ 1.
		נו	10		) ÷ 3] +	-	-	erals				at-grades
4.	Designer Select	ed Num	ber of 1	 Laterals		3	laterals	an engalangs	languaga ng tao	Grandens Sin	n Bea (1) (1) (1) (1) (1) (1)	
	Cannot be less		-		9	;)				per Per Person	Errick	
5.	Lateral spacing	in Bed;	Must be	greate	r than 1	foot an	d no more than .	2 feet fr	om Edg	e: [	3.2	0 ft
6.	Length of Later	rals = M	edia Bed	d Length	(2.) - 2	Feet.				_		
	85.0	- 2	ft =	8	3.0	ft <i>F</i>	Perforation can r	not be cl	oser the	en 1 foot	from (	edge.
7.	Select Perforat	ion Spac	ing:			3.0	ft					
8.	Determine the and round down	<i>Number</i> n to the	<i>of Perfo</i> nearest	oration ! whole n	<i>Spaces</i> . umber.	Divide	the Length of La	terals(6	.) by th	ne <i>Perfoi</i>	ration :	Spacing (7.)
	Number of Perf	oration	Spaces =	. 8	3.0	ft	÷ 3.0	ft	=	27	s	paces
9.	Number of Perf below to verify is double with a	the num	ber of p	perforati	equal to ions per	1.0 plu lateral	s the <i>Number of</i> guarantees less (	Perfora than a 10	<i>tion Spo</i> 0% disch	ices(8.) . large var	Check	( table
	Perforations Per Lateral = 27 Spaces + 1 = 28 Perfs. Per Lateral											
10.	Select Perforati	ion Diam	eter Siz	e:		7/32	in		0.21875	5		
11.	Select Lateral D	iameter	(See To	able):	Ī	2.00	in					
12.	Select Manifold	Connec	tion (En	d or Cer	nter):	END	If Ce			ection the e table car		nber of perfs
			ochuse de la conces	naspers var Sul	and the	Maintenant.						1885 - 17 E
		V Inch i	erforation						nch Perfo	rations		115 10 10 10 10 10 10 10 10 10 10 10 10 10
Perfor	ation Spacing (Feet)	1	Pipe E	Marneter (1 11/2	nches)	3	Perforation Spacing (Feet)			Diameter (Ir		
		and an arrangement of	NAME OF TAXABLE PARTY O				A STATE OF THE STA	44	11A	11/2	2	68
***************************************	21/1	В	12	16	28	54	2%	10	14	20	32	54
		CONTRACTOR DE COMMUNICACIONO				<b>A</b>			Н.,		30	40
-		3/16 Inch		ns Aumeter (ti	ochoe)		Hartanatan dan dan	1/8 (	nch Perfor			
Perfor	ation Spacing (Feet)	1	194	11/2	2	3	Perforation Spacing (Feet)	1	SNY SAME	Nameter (In	iches) 2	3
				KER	H. h	9						1402
5.94.101	ZA Distriction de la communicación	<b>12</b>	17 No.01 1996	24	<b>40</b> 23.466***********************************	80	212	20	30	41	69	135
	4.01上月10年1月1日					树之湖						



#### Pressure Distribution Design Worksheet

## MINNESOTA POLLUTION CONTROL AGENCY





# Basic STA Pump Selection Design Worksheet

- 76.M							
1. PUMP CAPACITY	Project ID:					v -	04.02.202
Pumping to Gravity or Pressure Distribution:	Pres	sure					
A. If pumping to gravity enter the gallon per minute of the	pump:		GPM (10 - 45	gpm)			
B. If pumping to a pressurized distribution system:		48.0	GPM				
C. Enter pump description:		Equ	alization/Time Do	sing			
2. HEAD REQUIREMENTS						Soll	Treatment Syste oint of discharg
A. Elevation Difference 12.0 ft							1505 kg
between pump and point of discharge:				Supply Wn	tengu		
B. Distribution Head Loss: 5 ft		Inter paper			Elevation difference		
C. Additional Head Loss*: It (due to	special equipment,	1 80		**********		<u>, , , , , , , , , , , , , , , , , , , </u>	
<ul> <li>Common additional head loss: gate valve = 1 ft each, globe valve valve = see manufacturers details</li> </ul>	e = 1.5 ft each, sp	litter		n ngangana	223460		
			Table ( Fricti	T			
Gravity Distribution - Oft	erical message in		Flow Rate (GPM)	1	e Diame 1.25	1.5	ies)
Pressure Distribution based on Minimum A	verage Hea	d	10	9.1	3.1	1.3	0.3
Value on Pressure Distribution Worksheet:		_	100	12.8	4.3	1.8	0.4
Manimum averagent estar most contr		visia 🖫	14	17.0 21.8	5.7 7.3	2.4 3.0	0.6
1ft 2ft	5ft 6ft		18	-149,	9.1	3.8	0.9
5ft	10ft		20	and services	in a	4.6	1.1
			25 30		16.8 23.5	6.9	1.7
D. 1. Supply Pipe Diameter: 2.0 in			35	A.A. (British)	23.3	9.7 12.9	2.4 3.2
2. Supply Pipe Length: 46 ft			40		Tariban Cariban	16.5	4.1
			45 50	Malacinia displaca		20.5	5.0
E. Friction Loss in Plastic Pipe per 100ft from Table I:			50 55		1. 150	73L	6.1
Friction Loss = 5.7 ft per 100ft of pip	oe e		60	estiller.	\$	1111	7.3 8.6
F. Determine Equivalent Pipe Length from pump discharge	to soil dispersal	area	65 70	4,000	77 III		10.0
discharge point. Estimate by adding 25% to supply pipe le Pipe Length X 1.25 = Equivalent Pipe Length	ength for fitting	g loss. Supply	75	-XXXX	in the M	V.4	11.4 13.0
The state of the s			85	California de la Califo			16.4
46 ft X 1,25 = 57.5	ift		95				20.1
G. Calculate Supply Friction Loss by multiplying Friction Los	s Per 100ft(E.)	by the Equival	ent Pipe Length(F	.) and div	ride by 10	0.	
Supply Friction Loss =			,				
5.7 ft per 100ft X 57.5	ft	÷ 100	= 3.3	ft			
Total Head requirement is the sum of the Elevation Diffe H. Supply Friction Loss(2G)	rence(2A) + Dis	stribution Head	Loss(2B) + Additi	onal Head	Loss(2C)	+	
12 ft + 5.0 ft	+	ft +	3.3 ft	- [	20.3	ft	
3. PUMP SELECTION							
A pump must be selected to deliver at least 48.	O GPM witi	h at least		20.3	feet	of total h	ead.
Comments:							
					-		



# STA Dosing Pump Tank Design Worksheet (Time Dose) MINNESOTA POLLUTION CONTROL AGENCY

					Proje	ect ID:					v 04.02.	202
ĎΕ	TERMI	INE TANK CAPACITY AND DIMENSI	ONS									
1.	A.	Design Flow:	750	GPD	В,	Tank l	Jse:		Equ	ualization		
	C.	Percentage of Design Flow 85	5 % 638	Gal	. Up to	75% de:	sign flov	w is norm	al for I	Design percei	ntage	
	D.	Code minimum pump tank capaci	ity: 750	Gal	E.			d capacity		2000	Gat	
2.	A.	Tank Manufacturer: BR	ROWN WILBERT	7	В.	Tank A	Model:			2000		-
	c.	Capacity from manufacturer:	2510	Gallon	ìS		Note: D	esign calc	ulations	s are based on	this specific tank	
	D.	Liquid depth of tank from manufa	acturer: 48.0	Inches	j.		float or	timer set	ferent ( tings, C	tank modet wi Contact design	ll change the pum er if changes are	p
	E.	Gallons per inch:	52.3	Gallon	ıs per ir	nch	песеѕѕа	ry.				
DET	ERMI	NE DOSING VOLUME										
		ne to Cover Pump (The inlet of pur	np should be 4 inches	from the	bottor	m of the	tank &	2 inches	coveri	ing the pump	recommended)	_
	Minin -Item	(Pump and block height + 2 inches)  ( 12	X 52.3 Gallo me of Distribution Pip Item 11 of Non-level	ons Per In	9.3			Gallons num dose	o [	3.24	inches/dose	
			0.25 =:	18	7.5	Callon	- /mavin	dona	Î	3.50	i ,,	
	_					1		num dose	) [	3.59	inches/dose	
		ct a pumpout volume that meets bu					Gallons			olume of	Liquid in	1
/. (	.altu	ate <i>Doses Per Day</i> = Percentage De	esign Flow(1C) ÷ <i>Deliv</i> 187.0 gal =	vered Voli		) Doses						
8. (	Calcul	ate Drainback;	501			DUSES					ara selek baran kacaman ber	
	١.	Diameter of Supply Pipe=		2	inches						ndicurdi. Rentoor	
E	3.	Length of Supply Pipe =		46	feet				(i	nches)	(callens)	
C	<b>.</b>	Volume of Liquid Per Lineal Foot	of Pipe = 0	0.170	Gallons	s/ft				1	0.045	
D	). 	Drainback = Length of Supply Pipe			i	_	Pipe(8C)	)		1.25	0.078	
		46 ft X 0.170			Gallons	5	•			1.5	0.110	
9. 7	otal L	Dosing Volume = Delivered Volume	7	1						2	0.170	
n v	Vorkin	187.0 gal + 7.8 ng Storage Volume = Tank Volume (	gal = 194.8	Gallons				<b>~~</b> \		3	0.380	
Γ		10.0 gai - 732.2 gal		152d		Gallons		,22.)	-	4		
			201.0		5.5	Gattona				4	0.661	
A. F 3. C	rom P alcula	ed Flow Rate:  Pump Curve - Must verify after Instated GPM = Change in Depth (in) x (  3.74 in X 5  Flow Rate from 11 A or B:		3		n Minute min = [	es 65.	.2		*Note: This must be adj after install based on p calibratio	usted lation ump	



# STA Dosing Pump Tank Design Worksheet (Time Dose) MINNESOTA POLLUTION CONTROL AGENCY

NORMAL OPERATION TIMER SETTINGS*		
13. Calculate <u>TIMER ON</u> setting*:		
Total Dosing Volume(9.) ÷ GPM(12.)	HR MIN	SEC
195 gal ÷ 50.0 gpm = 3.9 Minutes ON*	0 3.0	53 ON Time
14. Calculated TIMER OFF setting*:	<u> </u>	
Minutes Per Day (1440)/Doses Per Day(7.) - Minutes On(13.)	HR MIN	SEC
1440 min ÷ 3 doses/day - 3.9 min = 418.5 Minutes OFF*	6 58.0	30 OFF Time
OPTIONAL PEAK ENABLE DOSING* - Designers option for peak flow operation		
15. Peak Percentage of Design Flow		
16. Peak Pump Volume that meets both Minimum and Maximum Volume   gal + Drainback	7.8	gal
17. Peak Dose Volume gal HR	MIN SEC	13
18. Peak TIMER ON gal + gpm = min ON		Peak ON
*Note: This value must be adjusted after installation based on pump calibration.	MIN SEC	1
19. Peak TIMER OFF:1440 min ÷ doses/day - min On min Off		Peak OFF
FLOAT SETTINGS Alarm and Pump are to be wired on separate circuits and inspected by the electrical	l inspector	
20. Pump Off Float - Measuring from bottom of tank:		
Distance to set Pump Off Float=Gallons to Cover Pump(3.) + Gallons Per Inch(2E):		
732 gal ÷ 52.3 gal/in = 14.0 inches Reserve Capacity	251	Gal
Alarm Depth 43.2 in		
21. Alarm Float - Measuring from bottom of tank (90% recommended): Storage Capacity	1527	Gal
Distance to set Alarm Float = Tank Depth(2D) X % of Tank Depth (90% recommended) Normal Dose	407	
48.0 in X 90 % = 43.2 inches Volume	195	Gal
Pump Off 14.0 in	732	Gal
22. Reserve Capacity in gallons = Tank Depth(2D) - Alarm Depth(21.) X Gallons Per Inch(2E)		, 트
( 48.0 in - 43.2 in) X 52.3 = 251.0 gallons		



#### Tank Buoyancy Worksheet

_								
1.	Tank Specifications Project ID:			v 04.02.2024				
A.	Tank Manufacturer: BROWN WILBERT	Tank Model: 200	90					
В.	Outside Tank Dimensions and Specifications:	Tank Use:	Equalizati	on				
	Length: 144 in Width: 81 in Height: 65 in	Diameter:	in					
	Length: 12.0 ft Width: 6.8 ft Height: 5.4 ft	Radius of Tank:	ín					
2.	Outside Volume of Tank							
Г	Rectangular Tank		Circular Tank	(				
A.	Area of Tank = Length (ft) X Width (ft)	A. Area of Tank = $\pi r^2$ =						
	12.0 ft X 6.8 ft = 81.0 sq.ft	3.14 X (	ft) <sup>2</sup> =	sq.ft				
В.	Volume of Tank = Area of Tank (2.A) X Height (ft)	B. Volume of Tank = A						
	81.0 sq.ft X 5.4 ft = 438.8 cu.ft	sq.ft	t X	ft = cu.ft				
3.	Force of Tank Weight (F <sub>TW</sub> )							
	Weight of Tank (provided by manufacturer) 11550 lbs							
4.	Force of Soil Weight Over Tank (F <sub>sw</sub> )							
А. В.	Depth of Cover Over Tank:  27 in  2.3 ft  Weight of Soil Per Cubic Foot:  100 lbs/cu.ft		Soil Type	Weight of Soil (lbs/ft³)				
c.	Volume of Soil Over Tank = Depth of Cover(4A) (ft) X Area of Tank(2A) (	ft²)	Sandy	120				
	2.3 ft X 81.0 sq.ft - 182.3 cu.ft		Loamy	100				
D.	D. Weight of Soil Over Tank = Volume of Soil Over Tank(4C) X Weight of Soil Per Cubic Foot  Clay  90							
	182.3 cu.ft X 100 lbs/cu.ft = 18,225.0 lbs Nate: Ass	rumes saturation does not get						
5.B	uoyant Force (F <sub>B</sub> )							
	Buoyant Force ( $F_B$ ) = Outside Volume of Tank(2B) X Weight of Water Per 439 X 62.4 lbs/cu.ft X 1.2 = 32,853.6 lbs	Cubic Foot (62.4 lbs/ft <sup>3</sup> ) )	X 1.2 (Safety Factor)					
6. E	valuation of Net Forces							
A.	Downward Force = Force of Tank Weight (F <sub>TW</sub> )(3.) + Force of Soil Weight	of Soft (F <sub>SW</sub> )(4D.)		A Character of				
	11550 lbs + 18225 lbs = 29,775.0 lbs			Financy (Fa)				
В.	Net Difference = Downward Force(6A) - Buoyant Force Including Safety Force	actor (5.)		For + Fox > 1.2 x Fe Fox = Vsol x 80 fbs/f(3				
- [	29775 lbs - 32854 lbs = -3,078.6 lbs	Warning: Tank	=	Fw = Weight of tank Fs = Total tank volume x 62.4 Essiti (8.35 lbs/gal)				
	If the Net Difference is negative, counter measures will need to be taken Comments/Solution:	to prevent the tank from	n floating out of the	ground.				
- 1	I would recommend using 2 solid concrete Anchor blocks (2'x2'x6' = 3500	lb each) one on each side	with 4 inch strapp	oing over tank. Other				
	means of anchoring may be used to offset tank buoyancy		<b></b>	U TO THE STATE OF				
	•							
		8		//				



#### Tank Buoyancy Worksheet

1. Ta	ank Specifications Project ID:			. v 04	.02.2024
Α.	Tank Manufacturer: BROWN WILBERT	Tank Model: 250	20		7
В. (	Outside Tank Dimensions and Specifications:	Tank Use:	Septic		_
1	Length: 144 in Width: 81 in Height: 77 in	Diameter:	in		
1		_	=		
	Length: 12.0 ft Width: 6.8 ft Height: 6.4 ft	Radius of Tank:	in		
2. 01	Rectangular Tank		Circular Tank		
Α. Α	Area of Tank = Length (ft) X Width (ft)	A. Area of Tank = $\pi r^2$ =		ank) <sup>2</sup> )	
Г	12.0 ft X 6.8 ft = 81.0 sq.ft	3.14 X (	ft) <sup>2</sup> =	sq.ft	
B. V	Volume of Tank = Area of Tank (2.A) X Height (ft)	B. Volume of Tank = A			
	81.0 sq.ft X 6.4 ft = 519.8 cu.ft	sq.ft		t =	cu.ft
3. Force of Tank Weight (F <sub>TW</sub> )					
ν	Weight of Tank (provided by manufacturer) 16860 lbs				
4. Force of Soil Weight Over Tank (F <sub>SW</sub> )					
1	Depth of Cover Over Tank:  28 in  2.3 ft  Veight of Soil Per Cubic Foot:  100 lbs/cu.ft		Soil Type	Weight of Soil (lbs/ft³)	]
	/olume of Soil Over Tank = Depth of Cover(4A) (ft) X Area of Tank(2A) (	.c.2\			
Г	2.3 ft X 81.0 sq.ft = 189.0 cu.ft	TC-}	Sandy	120	
L			Loamy	100	
D. W	Velght of Soil Over Tank = Volume of Soil Over Tank(4C) X Weight of Soi	l Per Cubic Foot	Clay	90	
L	189.0 cu.ft X 100 lbs/cu.ft = 18,900.0 lbs Note: Ass	sumes saturation does not get	over the lid of the tank	Fini maga (Fi	- J
5.Buoyant Force (F <sub>B</sub> )					
	Subject to the following structure of Tank(2B) X Weight of Water Per $X = \frac{520}{20} \times \frac{62.4  \text{lbs/cu.ft}}{200} \times \frac{38,918.9}{200}  \text{lbs}$	Cubic Foot (62.4 lbs/ft <sup>3</sup> )	X 1.2 (Safety Factor)		
6. Evaluation of Net Forces					
A. D	ownward Force = Force of Tank Weight (F <sub>TW</sub> )(3.) + Force of Soil Weight	of Soil (F <sub>sw</sub> )(4D.)			
L	16860 lbs + 18900 lbs = 35,760.0 lbs			THE ENTRY PRODUCTION (Fig.	es present
B. N	et Difference = Downward Force(6A) - Buoyant Force Including Safety F	actor (5.)		Far + Fox > 1.2 x Fp For = Yssa x BO lbs/ft <sup>2</sup> For = Weight of land;	
L	35760 lbs - 38919 lbs = -3,158.9 lbs	Warning: Tanl	-	Fa = Total tank volume x	62.4 lbs/ft <sup>3</sup> 8.35 lbs/gal)
lf Co	If the Net Difference is negative, counter measures will need to be taken to prevent the tank from floating out of the ground.  Comments/Solution:				
- IN	I would recommend using 2 solid concrete Anchor blocks (2'x2'x6' = 3500 lb each) one on each side with 4 inch strapping over tank. Other				
m	means of anchoring may be used to offset pink buoyancy .				
L			-		