

**CONSTRUCTION OF SANITATION FACILITIES
PROJECT BE-21-L42
MILLE LACS INDIAN RESERVATION
PINE COUNTY, MINNESOTA**

**32586 HWY 123, Sandstone, MN
TIME DOSED TYPE III MOUND SYSTEM (REPLACE EXISTING SYSTEM)**

BID SCHEDULE

Schedule A - Individual Wastewater Facilities

ITEM NO.	DESCRIPTION	EST QTY	UNIT	UNIT COST	TOTAL COST
1	Mobilization	1	HR	_____	_____
2	Existing Mound Material Removal & Disposal	1	LS	_____	_____
3	Tank Pumping for Duration of Construction	1	LS	_____	_____
4	4-inch Schedule 40 PVC Gravity Pipe	23	LF	_____	_____
5	2-inch Schedule 40 PVC Force Main	46	LF	_____	_____
6	2-inch Schedule 40 PVC Perforated Lateral	249	LF	_____	_____
7	Two-way cleanout	1	EA	_____	_____
8	Brown-Wilbert 2500 Split Septic Tank	1	EA	_____	_____
9	Brown-Wilbert 2000 Pump Tank	1	EA	_____	_____
10	Tank Anchoring System (see design)	1	EA	_____	_____
11	Goulds WE511HH Effluent Pump	1	EA	_____	_____
12	SJE Rhombus Mod# IFS11W114H-8AC17G1J Time Dose Flow Control and Alarm	1	EA	_____	_____
13	Risers	15	VF	_____	_____
14	Polylok-122 Effluent Filter and Alarm	1	EA	_____	_____
15	Electrical Cable & Trenching	30	LF	_____	_____
16	Pine County ISTS Permit	1	EA	_____	_____
	Mound Materials				
17	Rock Bed	38	CY	_____	_____
18	Washed Sand	265	CY	_____	_____
19	Berm Material	315	CY	_____	_____
20	Topsoil	130	CY	_____	_____
21	Seed and Mulch	1	LS	_____	_____
				Subtotal	_____
				0.5% TERO	_____
				Total	_____

Contractor's Authorized Signature