

BID SCHEDULE
MILLE LACS BAND OF OJIBWE
INDIVIDUAL SEPTIC SYSTEM
FOR
39698 10TH AVE. ISLE, MN

SCHEDULE A: INDIVIDUAL SEWAGE TREATMENT SYSTEM

<u>LINE ITEM</u>	<u>ITEM DESCRIPTION</u>	<u>QUANTITY</u>	<u>UNIT</u>	<u>UNIT PRICE</u>	<u>ITEM TOTAL</u>
1	Mobilization	1	EA		
2	4-inch Schedule 40 PVC Gravity Pipe	42	LF		
3	2-inch Schedule 40 PVC Force Main	20	LF		
4	4-inch Schedule 40 PVC Insulated Pipe	10	LF		
5	2-inch Schedule 40 PVC Manifold Pipe	8	LF		
6	2-inch Schedule 40 PVC Perforated Lateral	108	LF		
7	Two-way Cleanout	1	EA		
8	Brown-Wilbert 1,000-gallon Pump Tank	1	EA		
9	Brown-Wilbert 2,000-gallon Combo Tank	1	EA		
10	Risers	4	EA		
11	Septic Tank Removal	1	LS		
12	SJE Rhombus EZP11W6C0H1JV8G10EP17A22C	1	EA		
13	Polyloc PL22 Effluent Filter and Alarm	1	EA		
14	Goulds WE511H Effluent Pump	1	EA		
15	Drainfield Gravel	10	CY		
16	Clean Sand	91	CY		
17	Mound Cover Sand	120	CY		
18	Mound Topsoil	62	CY		
19	Septic Permit	1	LS		
20	Electric Wiring and Hookup	1	LS		

TOTAL ESTIMATE

Completed items of work shall be measured and paid for in accordance with the requirements listed in the Bid Schedule. Payment shall be based on the actual quantities completed and shall represent full compensation under the contract. The price paid for the completed item of work shall include full compensation for furnishing all labor, materials, tools, equipment, and performing all work required by the provisions of the Contract. In all cases, the finished product shall be a completed operational system or component. The price for the complete item of work shall include all applicable taxes.

The Bid Schedule is based on estimated quantities required to meet the specifications. The total extended prices shall be used for bid evaluation purposes only. The actual amount to be paid under the contract shall be computed based on the actual quantities approved and installed at the unit bid price awarded. Bidder must bid on all items to be considered responsive, awarded will be for the aggregate of all items.

Bidder's Signature

Date

SECTION 01270 PRICE AND PAYMENT

PART 1 – GENERAL

1.01. SUMMARY

- A. Work covered by this section includes method of measurement and basis of payment for all divisions included.
- B. Payment for the various items of the Bid Schedules, as further specified herein, shall include all compensation to be received by the Contractor for furnishing all tools, equipment, materials, labor, supplies, manufactured articles, transportation, and temporary facilities required to complete the work in accordance with contract documents including incidentals.
- C. Respective prices and payment shall constitute full compensation for all work completed including incidentals.
- D. All items not expressly listed as being provided by others that are necessary for the completion of work shall be furnished and installed by the Contractor.

1.02. ESTIMATED QUANTITIES

- A. All quantities stipulated in the bid schedule or other contract documents are approximate and are to be used: (1) as a basis for estimating the probable cost of the work and (2) for the purpose of comparing the bids submitted.
- B. The Contractor shall be paid for actual quantities installed based on the quantities measured in the field. The actual amounts of work completed and materials furnished may differ from estimated quantities. The Contractor shall make no claim for damages, anticipated profits, or otherwise, on account of differences between the estimated amounts and the actual amount of work performed and materials furnished.

1.03. SURVEY AND MEASUREMENTS

- A. All quantity measurements shall be the responsibility of the Contractor and will be verified by the Engineer.
- B. All measurements and subsequent payments will be based on completed and accepted work performed in strict accordance with the drawings, specifications, and other contract documents.

PART 2 – BID SCHEDULE ITEMS

2.01. GENERAL

- A. Payment shall be full compensation to complete the work items in good faith, including incidental work.
- B. In addition to those things listed under each item, the unit price bid shall be full compensation for all of the following (unless otherwise expressly defined as a line item in the bid schedule):
 - 1. Submittals
 - 2. Record drawings
 - 3. Erosion control
 - 4. Clearing and grubbing
 - 5. Removal and replacement of obstructions
 - 6. Associated trenching, excavation and backfill including the removal of any nuisance water, bedding, haunching, and compaction.
 - 7. Disposal of any excess material
 - 8. Rough grading
 - 9. Finish work, where called for, including finish grading, topsoiling, and landscaping

2.02. BID ITEMS

Payment shall be as described below for all of the following items included on the Bid Schedule.

- A. Schedule A: Individual Wastewater Facilities
 - 1. Mobilization
 - a. Measurement: Lump Sum
 - b. Basis for Payment: Payment shall be full compensation for mobilizing and demobilizing.
 - c. restoration, and all other appurtenances required to complete the work as specified.
 - 2. 4-inch Schedule 40 PVC Gravity Pipe
 - a. Measurement: Linear feet

- b. Basis for payment: Includes all excavation, trenching, pipe, fittings, connections, tracer wire, bedding, haunching, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified.
- 3. 2-inch Schedule 40 PVC Force Main
 - a. Measurement: Linear feet
 - b. Basis for payment: Includes all excavation, trenching, pipe, fittings, connections, tracer wire, bedding, haunching, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified.
- 4. 4-inch Schedule 40 PVC Insulated Pipe
 - a. Measurement: Linear feet
 - b. Basis for payment: Includes all excavation, trenching, pipe, fittings, connections, tracer wire, bedding, haunching, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified.
- 5. 2-inch Schedule 40 PVC Manifold Pipe
 - a. Measurement: Linear feet
 - b. Basis for payment: Includes all excavation, trenching, pipe, fittings, connections, tracer wire, bedding, haunching, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified.
- 6. 2-inch Schedule 40 PVC Perforated Lateral
 - a. Measurement: Linear feet
 - b. Basis for payment: Includes all excavation, trenching, pipe, fittings, connections, tracer wire, bedding, haunching, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified.
- 7. Two-way Cleanout
 - a. Measurement: Each
 - b. Basis for payment: Includes all excavation, trenching, pipe, fittings, connections, tracer wire, bedding, haunching, backfilling, compacting,

final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified

8. Brown-Wilbert 1,000-gallon Pump Tank

- a. Measurement: Each
- b. Basis for payment: Includes all excavation, trenching, septic tank, fittings, connections, insulation, bedding, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified

9. Brown-Wilbert 2,000-gallon Combo Tank

- a. Measurement: Each
- b. Basis for payment: Includes all excavation, trenching, septic tank, fittings, connections, insulation, bedding, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified

10. Risers

- a. Measurement: Each
- b. Basis for Payment: Includes full compensation or furnishing and installing septic tank risers to ground level, and all other appurtenances required to complete the work as specified.

11. Septic Tank Removal

- a. Measurement: Lump Sum
- b. Basis for Payment: Includes full compensation to remove existing septic tank. Including all excavation, trenching, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified.

12. SJE Rhombus Model #EZP11W6COH1JV8G10EP17A22C

- a. Measurement: Each
- b. Basis for Payment: Includes full compensation to install septic control panel including all trenching, backfilling, compacting, final grading, seeding, site restoration, wiring, conduit, programing, and all other appurtenances required to complete the work as specified.

13. Polylok PL-122 Effluent Filter with Alarm

- a. Measurement: Each
- b. Basis for Payment: Includes full compensation to install the effluent filter including filter, alarm, wiring, conduit, weather seals, and all other appurtenances required to complete the work as specified.

14. Goulds WE0511H Effluent Pump

- a. Measurement: Each
- b. Basis for Payment: Includes full compensation to install the effluent pump including pump, wiring, conduit, riser block, pipe, fittings, and all other appurtenances required to complete the work as specified.

15. Drainfield Rock

- a. Measurement: Cubic Yards
- b. Basis for Payment: Includes full compensation to install drainfield rock including, all excavation, trenching, bedding, haunching, backfilling, compacting, final grading, and all appurtenances required to complete the work as specified.

16. Clean Sand

- a. Measurement: Cubic Yards
- b. Basis for Payment: Includes full compensation to install clean sand including, all excavation, trenching, bedding, haunching, backfilling, compacting, final grading, and all appurtenances required to complete the work as specified.

17. Mound Cover Sand

- a. Measurement: Cubic Yards
- b. Basis for Payment: Includes full compensation to install mound berm material including, all excavation, trenching, bedding, haunching, backfilling, compacting, final grading, and all appurtenances required to complete the work as specified.

18. Mound Topsoil

- a. Measurement: Cubic Yards
- b. Basis for Payment: Includes full compensation to install topsoil including, all excavation, trenching, bedding, haunching, backfilling, compacting, final grading, seeding, site restoration, and all appurtenances required to complete the work as specified.

19. Septic Permit

- a. Measurement: Lump Sum
- b. Basis for Payment: Includes full compensation for any and all city, county, and/or state permits required to complete the work as specified.

20. Electrical Wiring

- a. Measurement: Lump Sum
- b. Basis for Payment: Includes full compensation to wire and connect the control panel, pump and alarm to the fuse panel. Including all wire, trenching, bedding, haunching, backfilling, compacting, final grading, seeding, site restoration, and all other appurtenances required to complete the work as specified.

PART 3 – EXECUTION (N/A)

END OF SECTION