

**CONSTRUCTION OF SANITATION FACILITIES
PROJECT BE-23-L67
MILLE LACS INDIAN RESERVATION
AITKIN COUNTY, MINNESOTA**

**41936 248th Place, McGregor, MN 55760
TYPE I MOUND SYSTEM**

BID SCHEDULE

Schedule A - Individual Wastewater Facilities

ITEM NO.	DESCRIPTION	EST QTY	UNIT	UNIT COST	TOTAL COST
1	Mobilization	1	HR		
2	4-inch Schedule 40 PVC Gravity Pipe	40	LF		
3	2-inch Schedule 40 PVC Force Main	80	LF		
4	Insulated 2-inch Schedule 40 PVC Force Main	20	LF		
5	8-inch Dual Wall Corrugated PVC Culvert	20	LF		
6	2-inch Schedule 40 PVC Perforated Lateral	105	LF		
7	Two-way cleanout	1	EA		
8	Brown-Wilbert 2500 Split/Combo Septic Tank	1	EA		
9	Brown-Wilbert 1000 Pump Tank	1	EA		
10	Goulds WE511H Effluent Pump	1	EA		
11	SJE Rhombus Mod# EZP11W6COH1JV8G10EP17A22C	1	EA		
12	Risers	12	VF		
13	Polylok-122 Effluent Filter and Alarm	1	EA		
14	Electrical Cable & Trenching	70	LF		
15	Tank Abandonment	1	LS		
16	Aitkin County ISTS Permit	1	EA		
	Mound Materials				
17	Rock Bed	13	CY		
18	Washed Sand	183	CY		
19	Loam Cap	70	CY		
20	Topsoil	81	CY		
21	Seed and Mulch	1	LS		
22	Gravel Driveway Restoration	1	LS		

Sch. A Subtotal

Schedule B - Plumbing Subcontract

ITEM NO.	DESCRIPTION	EST QTY	UNIT	UNIT COST	TOTAL COST
1	Install Sewer Lift Pump and Connect To Sewer	1	LS		

Sch. B Subtotal

**0.5% TERO
Total**

Contractor's Authorized Signature