

**CONSTRUCTION OF SANITATION FACILITIES  
PROJECT BE-23-L67  
MILLE LACS INDIAN RESERVATION  
AITKIN COUNTY, MINNESOTA**

**424 7th Ave, Aitkin, MN 56431  
TYPE III MOUND SYSTEM**

**BID SCHEDULE**

**Schedule A - Individual Wastewater Facilities**

ITEM NO.	DESCRIPTION	EST QTY	UNIT	UNIT COST	TOTAL COST
1	Mobilization	1	HR		
2	4-inch Schedule 40 PVC Gravity Pipe	65	LF		
3	2-inch Schedule 40 PVC Force Main	45	LF		
4	2-inch Schedule 40 PVC Perforated Lateral	144	LF		
5	Two-way cleanout	1	EA		
6	Brown-Wilbert 2500 Split/Combo Septic Tank	1	EA		
7	Brown-Wilbert 1000 Pump Tank	1	EA		
8	Goulds WE511H Effluent Pump	1	EA		
9	SJE Rhombus Mod# EZP11W6COH1JV8G10EP17A22C	1	EA		
10	Risers	12	VF		
11	Polylok-122 Effluent Filter and Alarm	1	EA		
12	Electrical Cable & Trenching	70	LF		
13	Tank Abandonment	1	LS		
14	Aitkin County ISTS Permit	1	EA		
	Mound Materials				
15	Rock Bed	17	CY		
16	Washed Sand	330	CY		
17	Loam Cap	84	CY		
18	Topsoil	95	CY		
19	Seed and Mulch	1	LS		
				<b>Sch. A Subtotal</b>	
				<b>0.5% TERO</b>	
				<b>Total</b>	

\_\_\_\_\_  
Contractor's Authorized Signature